

DEPARTMENT OF GENERAL SERVICES
BUREAU OF PRE-CONSTRUCTION
1800 HERR STREETS
HARRISBURG, PENNSYLVANIA

ADDENDUM NO. 4

on

PROJECT NO. DGS C-0962-0029 PHASE 001

PROJECT TITLE - Rehabilitate Readiness Center, Hershey Readiness Center

PROFESSIONAL:

ByDesign Consultants, Inc.
1950 Market Street
Camp Hill, PA, 17011

SPECIFICATION CHANGES – ALL CONTRACTS

Item 1 - 10400: Replace last sentence in paragraph to read “Provide electrical, telephone, and internet service.”

Item 2 – 14000: Add Paragraph 1.3G:

“The Quality Control Agent shall submit a Testing and Inspection Plan to the Professional for its approval, and the approval of the Quality Assurance agent for all tests and inspections required by this section and within technical sections of the Project Manual.”

Item 3 – 14000: Add Paragraph 3.1N:

“All required testing/inspection, including that stated in the body of the technical specification sections (be it referenced in the technical specifications as “Quality Control”, “Quality Assurance”, or any other referenced testing and/or inspection) shall be performed by the Contractor, unless it explicitly states it shall be performed by the Department. If stated to be performed by the Department, the Contractor shall still be required to perform all necessary testing/inspection in advance of the Department to assure the work meets all the requirement of the contract documents.”

Item 4 – 14000: Add Paragraph 3.1O:

“Contractor shall coordinate closely with the Department, the Professional and the Professional’s QA Agencies and Consultants so that any required or desired QA testing can be performed concurrently or immediately after the Contractor’s QC testing.”

Item 5 – 14000: Add Paragraph 3.1P:

“The QC Agent shall cooperate in using standard forms/procedures developed by the Department that assist in accomplishing the tasks required.”

Item 6 – 15000: Add Paragraph 1.4N:

“The Lead Contractor shall provide electronic daily temperature/humidity readings equipment and log the conditions throughout the building to assure the proper and adequate temperature/humidity levels are recorded and maintained. The Lead Contractor shall provide the appropriate temporary ventilation, dehumidification, humidification or cooling equipment to assure the interior humidity/temperature levels are provided to meet all building finish requirements in accordance with the manufacture requirements.”