

William S Moorhead Federal Building Aesthetic and Safety Improvements

RLS Construction Group was contracted by the United States General Services Administration to install and repair sidewalk and bollards adjacent to the William S Moorhead Federal Building, in Pittsburgh, PA. The project will address increased site protection, as well as provide aesthetic improvements to the downtown site. The specific tasks involve installation of approximately ninety (90) bollards that extend along Grant Street, to the corner of Liberty Avenue, and along Liberty Avenue for the duration of the Federal Building property. The bollards will be rated to withstand a crash impact of 15,000-lbs at 30-MPH, and spacing will be coordinated with the Pittsburgh Area Transit bus stops. The end of each protected section will be closed off with an additional bollard placed midway between the curb and the building. Additional work will include the replacement of the terrazzo finish sidewalk along Liberty Avenue and Grant Street, to comply with current City of Pittsburgh design standards. Further improvements involve the replacement of approximately eleven (11) sections of existing granite curbing, to match the existing curbing in dimension, finish and color. The updated curbing includes the corner section, inscribed with "Grant Street and Liberty Avenue," which will be replicated to match the existing curb and inscription.



Location:
Pittsburgh, PA

Client:
US General Services Administration

Cost:
\$687,500

Completion Date:
on-going

RLS

CONSTRUCTION GROUP



- General Construction
- Design/Build
- Construction Management
- Building Maintenance

**Relationships
Loyalty &
Solutions**

A Service-Disabled Veteran-
Owned Small Business



www.RLSCG.com
717.502.6680