

Geo-Science Engineering & Testing, LLC

December 2, 2021

SMP Architects 1600 Walnut Street, #2 Philadelphia, Pennsylvania 19460

Attention: Todd Woodward, AIA, LEED AP

Reference: Supplemental Stormwater Infiltration Investigation @ Camp Shehaqua

Hickory Run State Park

White Haven, Pennsylvania 18661 GSET Project Number: 20030392

Mr. Woodward,

Geo-Science Engineering & Testing, LLC. (GSET) has completed a site evaluation for stormwater infiltration facilities for Latrine Improvements at the Hickory Run State Park in White Haven, Pennsylvania. All testing was conducted in general accordance with the Pennsylvania Department of Environmental Protection (PADEP)'s *Pennsylvania Stormwater Best Management Practices Manual*, *Appendix C – Site Evaluation and Soil Testing– December 2006* ("BMP Manual") specifications.

1.0 Project Site Conditions

The purpose of this evaluation was to determine feasibility for stormwater infiltration facilities in support of four, single-story Latrine Buildings and associated parking located throughout the Hickory Run State Park.

This site is designated as the Shehaqua site.

Currently, the dominant land use is that of walking/hiking trails, camping sites and natural setting. Visual inspection of the area also indicates manicured grasses, scrub grasses including upland habitat and mature canopy.

2.0 Testing Methods

In November 2021, two (2) additional test pits were excavated to evaluate and determine the suitability of the soils for stormwater infiltration. The test pit locations and depths were provided by Meliora. The location plan is attached to this report.

The soils were evaluated to determine if the soils have limitations that would affect the design, installation, and function of stormwater infiltration structures. Soil limitations are considered to be features such as a seasonal high water table, perched water table, restrictive soil horizons, massive bedrock, and fractured or open-jointed bedrock. The proposed infiltration sites are evaluated to determine feasibility and conformance to the BMP manual based on soil

morphology. The BMP manual recommends maintaining a two (2) foot separation from the bottom of the proposed infiltration structure and a soil limitation.

Upon documentation of conditions feasible for stormwater infiltration, infiltration tests are performed at the depth of the proposed infiltration structure. For this project, double ring infiltrometers were utilized for testing and are strongly preferred to percolation tests by PADEP for large basins because they discount the exfiltration of water from the sides of percolation holes and provide a much more accurate assessment of potential permeability. All infiltration tests should be performed within ± 1 ° of the design depth.

3.0 Results and Recommendations

Refer to the Test Location Plan, which shows the location of the test pits and infiltration testing. GSET completed a soil morphologic evaluation within each test pit, noting indications, if encountered, to the depth of redoximorphic features and soil horizons restrictive to infiltration based on soil morphology. Our findings are detailed in the Table 1, below.

Test Pit	Ex. Elev.	Test Elev.	Test Depth	Test Pit Depth	Limiting Zone	Field Infiltration Rate 1 (in/hr.)	Field Infiltration Rate 2 (in/hr.)	Field Infiltration Rate Avg. (in/hr.)
TP-8	1583	1581.6	1.4	3.4	NA	1.23	1.15	1.19
TP-9	1586	1581.25	4.75	6.75	NA	1.05	1.08	1.07

The infiltration values expressed in the table above represent actual field measurements, therefore it is recommended that a factor of safety of two (2) be applied to these rates. We also recommend performing post-construction infiltration testing in order to confirm your design parameters.

We appreciate the opportunity to work with you on this project and should you have any questions or require additional information please do not hesitate to contact our office.

Respectfully Submitted, Geo-Science Engineering Co., Inc

Jeremy C. Wint SR Soil Scientist

		LOG OF	TEST PIT TP-8R					
Date Ex	cavated:	11/9/21	Logged by:	JW		_		
Equipment:		Bobcat Mini Excavator	Surface Elevation(ft):		158	3.0		
DEPTH (feet)	GRAPHIC LOG	MATERIAL DI		SAMPLE	HAND PEN. (tsf)	MOISTURE (%)	DRY UNIT WT. (pcf)	LAB TESTS
	11 711 711 71 71 71	Root mat - O - Silty Sand - Brown w						
	00000	SILTY SAND with GRAVEL (SM)	brown - medium dense, moist					
	0 0	Infiltration Test Elevation SILTY SAND with GRAVEL (SM)	- red brown dense moist	7				
	0.0000000		red erown, derise, moise					
		EOP @ 3.4'						

TEST_PIT 20030392 TP.GPJ LAGNNN07.GDT 12/2/21

Geo-Science Engineering & Testing, LLC 1252 Mid Valley Drive Jessup, PA 18434 Phone: 570-489-8717 Fax:

Hickory Run State Park White Haven, PA

Project Name: Hickory Run State Park

Project #: 20030392

Date: 11/9/2021


Location: TP-8R

Surface Elevation = 1583

Depth of Test = 1.4 feet

Testing Equipment = Double Ring Infiltrometer

Time	Reading		
(min)	(mm)	(inches)	(in/hr)
30	19	0.75	1.50
60	18	0.71	1.42
90	16	0.63	1.26
120	13	0.51	1.02



Average of last 4 = 1.23 in/hr

Project Name: Hickory Run State Park

Project #: 20030392

Date: 11/9/2021


Location: TP-8R(2)

Surface Elevation = 1583

Depth of Test = 1.4 feet

Testing Equipment = Double Ring Infiltrometer

Time	Reading		
(min)	(mm)	(inches)	(in/hr)
30	18	0.71	1.42
60	17	0.67	1.34
90	14	0.55	1.10
120	13	0.51	1.02



Average of last 4 = 1.15 in/hr

		LOG OF TEST P	TT TP-9R					
Date Excavated:		11/9/21	Logged by:	W		_		
Equipment:		Bobcat Mini Excavator	Surface Elevation(ft):	1586.0				
DEPTH (feet)	GRAPHIC LOG	MATERIAL DESCRIPTION	1	SAMPLE	HAND PEN. (tsf)	MOISTURE (%)	DRY UNIT WT. (pcf)	LAB TESTS
\(\frac{1}{2}\)	711/ 711/	Root mat - O - Silty Sand - Brown w/root mat						
- 	0 0 0 0	SILTY SAND with GRAVEL (SM) brown - medi						
	000000	SILTY SAND with GRAVEL (SM) red brown, m dense, moist						
- 5 -	00000000	Infiltration Test Elevation						
		EOP @ 7'						

TEST_PIT 20030392 TP.GPJ LAGNNN07.GDT 12/2/21

Geo-Science Engineering & Testing, LLC 1252 Mid Valley Drive Jessup, PA 18434 Phone: 570-489-8717 Fax:

Hickory Run State Park White Haven, PA

Project Name: Hickory Run State Park

 Project #:
 20030392

 Date:
 11/9/2020


 Location:
 TP-9R

Surface Elevation = 1586

Depth of Test = 4.8 feet

Testing Equipment = Double Ring Infiltrometer

Time	Reading		
(min)	(mm)	(inches)	(in/hr)
30	21	0.83	1.65
60	17	0.67	1.34
90	15	0.59	1.18
120	14	0.55	1.10
150	11	0.43	0.87



Average of last 4 = 1.05 in/hr

Project Name: Hickory Run State Park


Project #: 20030392
Date: 11/9/2020
Location: TP-9R(2)

Surface Elevation = 1586


Depth of Test = 4.8 feet

Testing Equipment = Double Ring Infiltrometer

Time	Reading		
(min)	(mm)	(inches)	(in/hr)
30	20	0.79	1.57
60	16	0.63	1.26
90	16	0.63	1.26
120	13	0.51	1.02
150	12	0.47	0.94




Average of last 4 = 1.08 in/hr




TB-4 GEOTECHNICAL TESTING PLAN 1'=20' SHEHAQUA

- 1. ALL TEST BORINGS SHALL BE CARRIED TO THE DEPTHS LISTED IN THE SCHEDULE, EXCEPT WHERE ROCK IS ENCOUNTERED PRIOR THERETO, IN WHICH CASE, CORING SHALL EXTEND (5) FEET INTO THE ROCK, WHETHER OR NOT THE FINAL DEPTH IS MORE OR LESS THAN THE DEPTH LISTED IN THE SCHEDULE, EXCEPT THAT CERTAIN BORINGS SHALL BE CARRIED TO THE CONTRACT DEPTH REGARDLESS OF THE MATERIALS ENCOUNTERED.
- 2. ALL INFILTRATION TESTS SHALL BE DOUBLE-RING INFILTROMETER SCHEDULE. TESTING REQUIREMENTS SHALL FOLLOW PA STORMWATER BMP MANUAL AND KIDDER TOWNSHIP CODE CHAPTER 148.







1600 WALNUT STREET, SECOND FLOOR PHILADELPHIA, PENNSYLVANIA

COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES

HARRISBURG, PENNSYLVANIA D.G.S. PROJECT No. C-114-0006 PHASE

VERIFY SCALE BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING: IF BAR IS NOT ONE (1) INCH LONG

ADJUST SCALE ACCORDINGLY CONTRACTOR SHALL FIELD VERIFY DRAWN BY ALL DIMENSIONS.
VARIANCE FROM CONTRACT M DIMONTE DOCUMENTS NOT PERMITTED CHECKED BY WITHOUT PROFESSIONAL & BUREAU M DIMONTE OF CONSTRUCTION APPROVAL.

HICKORY RUN STATE PARK LATRINE IMPROVEMENTS DEPT of CONSERVATION AND NATURAL RESOURCES WHITE HAVEN, CARBON COUNTY, PA TEST BORING LOCATION PLAN AND SCHEDULE - SHEET 5 10/30/2020

AS NOTED

TB-4

of XX FILE