

**Monroe County Historical Association Alteration & Heritage Center Addition
900 Main Street, Stroudsburg, PA 18360**

This Addendum forms part of the Contract Documents and modifies the original Bidding documents dated January 26, 2023 as noted below. Acknowledge receipt of this Addendum by inserting its number and date in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification. This addendum consists of two (2) page(s) and attachments as listed.

I. CHANGES TO THE PREVIOUS ADDENDA

N/A

II. GENERAL INFORMATION

GC shall install and maintain 1/8" hardboard (or equal) type floor protection with taped joints at existing building areas requiring access to complete work. GC shall cordon off and restrict construction workers from existing building areas not requiring construction access.

III. CHANGES TO BIDDING REQUIREMENTS

N/A

V. CHANGES TO THE SPECIFICATIONS

Section 28 2310 CCTV System (Construction Phase), REPLACE Section 2.4, in its entirety, with the following temporary construction security system scoping requirements:

2.4 CAMERAS

- A. Indoor Dome Cameras: Fixed Dome, 8MP, Infrared, onboard analytics, PTZ; Capture, encode and transmit video over a network.
 - 1. Provide cameras in the following locations:
 - a. Provide (1) in each of the following existing rooms: 101, 103, 104, 201, 202, 301 & 303. Please note the above (7) rooms will have owner furnishings consolidated and protected with a taped plastic cover All other rooms will be emptied by the owner prior to construction start.
 - b. Provide (5) additional cameras at hallways and entrances/exits.
- B. Outdoor Dome Cameras: Fixed Dome, 8MP, Infrared, onboard analytics, PTZ; Capture, encode and transmit video over a network.
 - 1. Provide an exterior camera at each exit from the building. In addition, provide a minimum of (1) camera on each side of the building.
- C. Owner requested Cameras: Coordinate system with owner and project team prior to ordering. Layout is subject to review by owner's rep.

VI. CHANGES TO THE DRAWINGS

A100 CLARIFY basement ramp CIP conc. stairs receive 1-1/2" diameter st. steel pipe handrail wall-mounted where adjacent to a partition. Ref. 6/A332 & 2/A322. Where there is no adjacent partition, provide steel guardrail & 1-1/2" diameter st. steel pipe handrail. Ref 4/A332 & 2/A322.

- A101 CLARIFY stair in 106 Gift Shop receives 1-1/2" diameter st. steel pipe handrail wall-mounted, both sides. Ref. 6/A332 & 2/A322.
- A500 CLARIFY LVT-1 floor finish on ramp & CIP conc. stairs.
- A501 CLARIFY LVT-1 on stairs in 106 Gift Shop.

ATTACHMENTS – The following are attached hereto and made a part of the contract documents:

Minutes:

N/A

Specifications:

N/A

Sketches:

N/A

Drawings:

N/A

END OF ADDENDUM No. 3