

DATE: February 6, 2024

DEPARTMENT OF GENERAL SERVICES  
BUREAU OF CAPITAL PROJECT DESIGN MANAGEMENT  
1800 HERR STREET  
HARRISBURG, PENNSYLVANIA

**ADDENDUM NO. 5**

**on**

**PROJECT NO. DGS C-0946-0012 PHASE 004**

**PROJECT TITLE - PA State Museum and State Archives - Renovations and Upgrades**

**PROFESSIONAL:**

Vitetta Group, Inc.

645 North 12th Street

Lemoyne, PA, 17043

**If you submitted a bid prior to this Addendum being issued, your bid has been discarded and you must re-submit your bid(s) prior to the bid opening date and time.**

SPECIFICATION CHANGES – ALL CONTRACTS

Item 1 - Specification Section 017100 "Removal of Asbestos-Containing Materials": Clarified ACM ceiling finish abatement quantities. Refer to attached Page 017100-2.

- a. 1<sup>st</sup> Floor: Friable asbestos acoustical ceiling finish on gypsum plaster is present. There is approximately 314 sf of acoustical ceiling finish located in the Village Square Exhibit 103 and 860 sf Changing Exhibits 128.
- b. 2<sup>nd</sup> Floor: Friable asbestos acoustical ceiling is present. There is approximately 635 sf of ceiling finish located in Transportation Exhibit 217.
- c. 4<sup>th</sup> Floor: Friable asbestos acoustical ceiling finish on gypsum plaster is present. There is approximately 277 sf of ceiling finish at Office 412.
- d. 5<sup>th</sup> Floor:
  - 1) Friable asbestos acoustical ceiling finish on gypsum plaster is present. There is approximately 15 sf each for a total of 30 sf.

4. The following table lists ACM types and quantities.

**ACM Totals**

Material	Floor	Location	Exhibit/Office	Quantity (sf)	Total
1. Ceiling Finish	1 <sup>st</sup>	103	Village Square	314	2,809
	1 <sup>st</sup>	128	Changing Exhibits	860	
	1 <sup>st</sup>	110	Coats	420	
	2 <sup>nd</sup>	217	Transportation Exhibit	635	
	4 <sup>th</sup>	408	Office	273	
	4 <sup>th</sup>	412	Office	277	
	5 <sup>th</sup>	Outside 506	Hallway outside office	15	
	5 <sup>th</sup>	Outside 526	Hallway outside office	15	

1.3 CONTROL OF WORK

- A. All work which does not conform to the requirements of the contract, plans and specifications will be considered unacceptable.
- B. Unacceptable work, whether the result of poor workmanship, use of defective materials, damage through carelessness, or any other cause found to exist prior to the final acceptance of the work, shall be corrected immediately and replaced in an acceptable manner.
- C. All Proposers are encouraged to visit the job site prior to bidding to determine job conditions.
- D. If the Department finds the materials furnished, work performed, or the finished product not within reasonably close conformity with the plans and specifications and have resulted in an unacceptable finished product, the affected work or material shall be removed and replaced or otherwise corrected by and at the expense of the Contractor.