



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

1511 Route 22, Suite C24, Brewster, NY 10509  
Phone: 845.278.7710 Fax: 845.278.7750

**Project: Main Building, 1<sup>st</sup> Floor**  
VA Medical Center  
Wilkes-Barre, PA 18711

**Inspector(s):** James Reber  
Thomas Ferro  
**Date(s):** 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
<b>1<sup>st</sup> Floor, W wing, room C1-01</b>						
Floor	Rug over red brown 9" X9" floor tile	280 ft <sup>2</sup>	N/A	4/12-03	N/A	<b>15% Chrysotile</b>
Walls	Sheetrock/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64ft <sup>2</sup>	Damaged			<b>Assumed</b>
<b>1<sup>st</sup> Floor, W wing, room C1-02 (suite)</b>						
Floor	Rug over floor tile	360 ft <sup>2</sup>	N/A	4/12-01	N/A	<b>3% Chrysotile</b>
	Mastic	360 ft <sup>2</sup>	N/A	4/12-02	N/A	<b>10% Chrysotile</b>
Walls	Sheetrock/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	V	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, room C1-03</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile	160 ft <sup>2</sup>	N/A	N/A	Prev. tested pos.	<b>&gt;1%</b>
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	Prev. tested pos.	<b>&gt;1%</b>

**VA Medical Center, Main Building, 1<sup>st</sup> Floor**

Adelaide Environmental Health Services, Inc. – Project No. VAMC:10013.00-IN



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (above 2' X 4')	160 ft <sup>2</sup>	N/A	N/A	1-195	None detected
Univents	Transite panels	20-40 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C-1-03A</b>						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" floor tile and mastic	200 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (off white w/ grainy surface) – above 2' X 4'	N/A	N/A	1-195	N/A	None detected
Univents	Transite panels	20-40 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, W wing, room C1-05 (suite) – 05 , 06, 07, 08, 09, 10, 11, 12, 13</b>						
Floor	Rug over concrete or platform	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles ( white w/rows of holes) – above 2' X 4'	N/A	N/A	N/A	1-187	None detected
Univents	Transite panels (one front panel missing)	100-200 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Over ceiling, far S wall	Duct insulation (black mastic over cork)	Not found	N/A	N/A	6-96	<b>Not found</b>
Chases + over ceiling in room next to ladies room	Pipe insulation (C1-11)	12 LF	Good	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, W wing, ladies' (C1-14) and men's (C1-15) rooms across from C1-05</b>						
In wall between mens/ladies rooms	Pipe insulation	5 LF	Good	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, W wing, electrical closet (E of stair #1)</b>						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	<b>8% Chrysotile</b>
<b>1<sup>st</sup> Floor, room C1-18</b>						
Floor	12" X 12" floor tile (light gray w/white dark gray mottles)	100 ft <sup>2</sup>	N/A	N/A	6-105	None detected
	Floor tile mastic	100 ft <sup>2</sup>	N/A	N/A	6-106	<b>5% Chrysotile</b>
Ceilings	2' X 2' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-19</b>						
Floor	<del>Rug over leveling compound over black mastic - Removed</del>	N/A	N/A	N/A	N/A	N/A
	<del>Black mastic - Removed</del>	150 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, rooms C1-21B and C1-21C and C1-20</b>						
Floor	<del>Rug over floor tile - Removed</del>	N/A	N/A	N/A	N/A	N/A
	<del>12" X 12" floor tile - Removed</del>	150 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, W wing, room C1-21A - Removed and is part of C1-22A now</b>						
Floor	12" X 12" floor tile (white w/olive mottles) - Removed	525 ft <sup>2</sup>	N/A	N/A		<b>N/A</b>
	Floor tile mastic - Removed	525ft <sup>2</sup>	N/A	N/A		<b>N/A</b>
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, room C1-22A (and also C1-21B and C1-21C)</b>						
Floor (raised floor; tiles not found underneath)	12" X 12" floor tile (off-white w/tan & brown streaks) - Removed	N/A	N/A	N/A	6-103	<b>5% Chrysotile</b>
	Floor tile mastic - Removed	N/A	N/A	N/A	6-104	<b>5% Chrysotile</b>
Walls	Sheetrock	N/A	N/A	N/A	Previously tested positive	<b>&gt;1%</b>
Ceilings	2' X 4' ceiling tiles - removed	N/A	N/A	N/A	Previously tested positive	<b>&gt;1%</b>
<b>1<sup>st</sup> Floor, room C1-22</b>						
Floor	12" X 12" floor tile (white w/brown streaks) –E room (C1-22D)	150 ft <sup>2</sup>	N/A	N/A	6-103	<b>5% Chrysotile</b>
	Floor tile mastic	150 ft <sup>2</sup>	N/A	N/A	6-104	<b>5% Chrysotile</b>
	12" x 12" floor tile (off white w/tan marks) –W room	150 ft <sup>2</sup>	N/A	N/A	3-165	None detected
	Floor tile mastic- W room	150 ft <sup>2</sup>	N/A	N/A	3-166	<b>5% Chrysotile</b>
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>C1-22E has pipe insulation – 8 LF, good. Same floor tiles as C1-22 – 484 ft<sup>2</sup>. Has suspect drywall on S wall - 30ft<sup>2</sup>, damaged</b>						



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, mechanical room behind C1-22 (on drawings as C1-22C)</b>						
Floor	12" X 12" floor tile (off-white w/tan marks)	400 ft <sup>2</sup>	N/A	N/A	3-165	None-detected
	Floor tile mastic	400 ft <sup>2</sup>	N/A	N/A	3-166	<b>5% Chrysotile</b>
<b>1<sup>st</sup> Floor, room C1-23</b>						
Floor	Rug	N/A	N/A	N/A	N/A	Non-suspect
	12" X12' floor tile	400 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	400 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles & plaster	Pipe insulation	10 LF	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-24 and C1-27 (Armory)</b>						
Floor	12" X 12" floor tile (off white w/tan & dark tan mottles)	N/A	N/A	N/A		Non-suspect
	Floor tile mastic	N/A	N/A	N/A		Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels ( front panels removed)	24-48 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Chases	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, room C1-28</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" floor tile and mastic - Removed	200 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off white w/random pock markings)	200 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, Room C1-32</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile- new	V	V	V	V	Non-suspect
Chases	Pipe insulation – no view in chases	indeterminate	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, rooms C1-32-A and C1-32B – No suspect materials observed</b>						



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, E wing, room C1-30</b>						
Floor	9" X 9" floor tile (brown)	25 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	25 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, E wing, room C1-35A</b>						
Pipes	Pipe insulation (black mastic over cork)	12 LF	N/A	N/A	6-96	<b>8% Chrysotile</b>
<b>1<sup>st</sup> Floor, rooms C1-36 and C1-37</b>						
Ceilings	12" X 12" ceiling tiles (white, perforated)	20-30 ft <sup>2</sup>	N/A	1-187	N/A	None detected
	2' X 2' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	Ceiling tile mastic	20-30 ft <sup>2</sup>	N/A	1-188	N/A	None detected
Univents	Transite panels	32-64 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, E wing, room C1-36A</b>						
S wall	Pipe insulation	30 LF	Significant damage	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Comments: Behind the plaster fascia, there is a pipe chase which runs E to W on the S wall. Suspect pipe insulation may exist within the chase, and this situation may exist in all rooms within this area						
<b>1<sup>st</sup> Floor, room C1-38</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tiles- new and 12" X 12"	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	40 – 80 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, E wing, rooms C1-43,C1-44, C1-45, C1-51, C1-52, 56A – No exposed suspect asbestos materials observed</b>						
<b>1<sup>st</sup> Floor, E wing, rooms C1-39, C1-40, C1-41, &amp; C1-42</b>						
Univents	Transite panels	50 ft	Damaged	N/A	N/A	<b>Assumed</b>
Comments: Except for C1-42, the front transite panels have been removed. The rear could not be observed at the time of this inspection and could be present.						
<b>1<sup>st</sup> Floor, room C1-53</b>						
Pipe in SW corner	Pipe insulation in chase- can't see condition	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-54</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation (SE corner)	5 LF	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-56-B, C1-56C (Corridors)</b>						
Floors	12" X12" floor tile-Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile mastic	N/A	N/A	N/A	N/A	N/A
Walls	Plaster/	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile over fireproofing	N/A	N/A	N/A	N/A	Non-suspect





**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, C1-56</b>						
Floor	12" X 12" floor tile (brown w/ white, gray and dark brown marble effect)	480 ft <sup>2</sup>	N/A	N/A	1-01	None detected
	Floor tile mastic	480 ft <sup>2</sup>	N/A	N/A	1-02	<b>3% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (concrete deck)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (runs down into SW wall)	15-20 LF	Significant damage	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	32-64 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-55</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12 X 12" floor tile	160 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, smoking area NOT FOUND – Non-existing</b>						
Floor	12" X 12" floor tile (off-white w/ tan & dark tan mottles)	625 ft <sup>2</sup>	N/A	8-281	N/A	None detected
	Floor tile mastic	625 ft <sup>2</sup>	N/A	8-282	N/A	<b>&lt;1% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	12" X 12" ceiling tile	N/A	N/A	8-283	N/A	None detected



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, room C1-59</b>						
Floor	12" X 12" floor tile (off-white w/gray mottles) and mastic	115 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above & behind plaster	Pipe insulation	20-30 LF	N/A	N/A	v N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, ladies room (C1-60) &amp; men's room (C1-61) plus C1-58 (vestibule)</b>						
Above ceiling and in walls where it was partially removed and replaced w/ fiberglass	Pipe insulation	N/A	Damaged	N/A	N/A	<b>Assumed</b>
Comment: C1-58 vestibule – 18 LF of pipe (aircell). Nothing above men's room/no access to ladies room ceiling						
<b>1<sup>st</sup> Floor, room C1-62</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, room C1-63</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, C1-64</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (white w/ striations)	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, room C1-65, C1-66, C1-67, C1-68</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	Previously tested	Non-suspect
Comments: In rooms C1-63 through C1-68, suspect asbestos insulation possible on pipes above plaster ceiling						
<b>1<sup>st</sup> Floor, W wing, room C1-70</b>						
Floor	Rug over 12" X 12" floor tiles/mastic	185 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assume</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, room C1-71 and C1-70-A</b>						
Floor	Rug over brown 9X9 floor tile and mastic	360 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tile (white w/rows of holes) – above 2' X 4'	160 ft <sup>2</sup>	N/A	N/A	1-187	None detected



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, W wing, room C1-72</b>						
Floor	Rug over leveling compound and brown 9X9 floor tile and mastic	180 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
	Sheetrock joint material	N/A	N/A	1-196	N/A	None detected
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (off-white w/ holes) – above 2' X 4'	150 ft <sup>2</sup>	N/A	N/A	1-187	None detected
<b>1<sup>st</sup> Floor, W wing, rooms C1-74a, C1-74, &amp; C1-73</b>						
Floor	Rug over brown 9X9 floor tile and mastic	450 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles (white w/rows of holes) – above 2'X4'	380 ft <sup>2</sup>	N/A	N/A	1-187	None detected
Comments: No access under rug at the time of this inspection – possible floor tile and mastic materials under rug. Checked – Floor tile found						
<b>1<sup>st</sup> Floor, room C1-76</b>						
Pipes	Pipe / fitting insulation	4-6 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, room C1-77</b>						
Floor	9" X 9" floor tile (white w/ black flecks)	110 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor I - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, hall by main elevator</b>						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Marble	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, main hall (mental health to Chapel Hall) (C1-18)</b>						
Floor	12" X 12" floor tile (tan w/ white/dark tan mottles)	2696 ft <sup>2</sup>	N/A	N/A	8-039	None detected
	Floor tile mastic	2696 ft <sup>2</sup>	N/A	N/A	8-040	<b>2% Chrysotile</b>
<b>1<sup>st</sup> Floor, security locker room by stair # 3 (C1-78)</b>						
Floor	12" X 12" floor tile (chocolate w/ white/brown marble effect)	40 ft <sup>2</sup>	N/A	N/A	7-86	None detected
	Floor tile mastic	40 ft <sup>2</sup>	N/A	N/A	7-87	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	4 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, N1-71 ( Not on plans or in field)</b>						
Floor	Rug over leveling compound	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/carpeted panels	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation	8 LF	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite Panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room N1-80</b>						
Floor	12" X 12" floor tile ( off-white w/ light & dark olive mottles)	216 ft <sup>2</sup>	N/A	N/A	1-286	<b>5% Chrysotile</b>
	Floor tile mastic	216 ft <sup>2</sup>	N/A	N/A	1-287	<b>3% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, N wing, room N1-81 ( room N of N1-80)</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white w. light & dark olive mottles)	300 ft <sup>2</sup>	N/A	N/A	1-286	<b>5% Chrysotile</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	N/A	1-287	<b>3% Chrysotile</b>
Walls	Plaster/Sheetrock	N/A	N/A	N/A	∇	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles & above E wall & duct	Pipe insulation	< 25 LF	FN/A	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-86D</b>						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non- suspect
	12" X 12" floor tile ( white w/ black streaks	560 ft <sup>2</sup>	N/A	N/A	8-028	<b>10 % Chrysotile</b>
	Floor tile mastic	560 ft <sup>2</sup>	N/A	∇	8-029	<b>5% Chrysotile</b>
Walls	Plaster/ sheetrock	N/A	N/A	N/A	N/A	Non- suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non- suspect
Above ceiling tile	Pipe insulation	20-25 LF	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	64-128 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room just S of N1-81</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-Suspect
	12' x 12" ( off-white w/ light and dark olive mottles)	160 ft <sup>2</sup>	N/A	N/A	1-286	<b>5% Chrysotile</b>
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	1-287	<b>3% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation	8-10 LF	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N 1-82</b>						
Floor	12" X12" Floor tile ( off-white w/ light & dark olive mottles)	80-100 ft <sup>2</sup>	N/A	1-286	N/A	<b>5% Chrysotile</b>
	Floor tile mastic	80-100 ft <sup>2</sup>	N/A	1-287	N/A	<b>3% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" x 12" ceiling tile (white w/ rows of holes) –above 2' X 4'	N/A	N/A	N/A	Previously tested	<1%
<b>1<sup>st</sup> Floor, N wing, room N1-83</b>						
Floor	Carpet over 12" X12" floor tile (tan w/ white/dark tan mottles)	250 ft <sup>2</sup>	N/A	N/A	8-039	None detected
	Floor tile mastic	250 ft <sup>2</sup>	N/A	N/A	8-040	<b>2% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile/plaster ceiling	Pipe insulation (can't see above plaster)	N/A	N/A	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room N1-85</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Marble/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	216 ft <sup>2</sup>	Damaged	N/A	2-121	<b>5% Chrysotile</b>
Comments: No access above ceiling tiles within this area due to the asbestos content of the ceiling tiles.						
<b>1<sup>st</sup> Floor, N wing, room N1-86 and Mechanical room Labeled N1-89 on drawings(which is labeled twice)</b>						
Floor	12" X 12" floor tile (white w/tan & dark tan mottles)	960 ft <sup>2</sup>	N/A	N/A	5-69	None detected
	Floor tile mastic	960 ft <sup>2</sup>	N/A	N/A	5-70	<b>5% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Ceiling tile - Removed					N/A
Above ceiling tile	Pipe/fitting insulation (N1-86)	20-25 LF	Damaged	N/A	N/A	<b>Assumed</b>
Pipes in Mech N1-89	Valve Fitting Insualtion	1 LF	Significant Damage	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	64-128 ft <sup>2</sup>	Damaged	V	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-89 (Room between N1-86D and N1-79)</b>						
Floor	12" X12" floor tile under rug	250 ft <sup>2</sup>	N/A	N/A	1-286	<b>5% Chrysotile</b>
	Mastic	250 ft <sup>2</sup>	N/A	N/A	1-287	<b>3% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In chase	Pipe/fitting insulation	20-30 LF	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>





**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room N1-91</b>						
Pipe riser	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	6-96	<b>8% Chrysotile</b>
<b>1<sup>st</sup> Floor, N wing, room N1-92 and N1-93 (bathroom)</b>						
Floor	12" X 12" floor tile (gray/green w/ white & gray mottles) - Removed	160ft <sup>2</sup> (N1-92) 50ft <sup>2</sup> (N1-93)	N/A	1-190	N/A	N/A
	Floor tile mastic - Removed	160 ft <sup>2</sup>	N/A	1-191	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile and plaster	Pipe insulation	>30 LF	Good	N/A	N/A	<b>Assumed</b>
Univents (N1-92 only)	Transite panels	16-32 ft <sup>2</sup>	Significant damage	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-95 and N1-94 (bathroom)</b>						
Floor	12" X 12" floor tile (gray/green w/ white & gray mottles)	150 ft <sup>2</sup>	Good	N/A	1-190	<b>5% Chrysotile</b>
	Floor tile mastic	150 ft <sup>2</sup>	N/A	N/A	1-191	<b>10% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile (over W wall)	Pipe insulation	20 LF	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, rooms N1-99, N1-100, N1-102A, N1-102, N1-103A, N1-103 and N1-104A</b>						
Floor	9" X9" floor tile (white w/blue marks)	~160 ft <sup>2</sup> /area	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	~160 ft <sup>2</sup> /area	N/A	N/A	N/A	<b>Assumed</b>
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
In chases ( all rooms) & above ceiling tile in 99,102,103A- removed above ceilings	Pipe insulation – 103A No pipe above, 102 8in damage piece B4 chase, 99 can't see/plaster ceiling	20-30 LF each	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (103 & 103A 3 of 4 front panels gone)	16-32 ft <sup>2</sup> /area	Damage	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, rooms N1-104B and N1-104</b>						
Floor	12" X 12" floor tile (gray w/ white and dark gray mottles)	160 ft <sup>2</sup> /area	N/A	N/A	8-039	None detected
	Floor tile mastic	160 ft <sup>2</sup> /area	N/A	N/A	8-040	<b>2% Chrysotile</b>
	9" X 9" floor tile (N1-104B)	4-5 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	16-32ft <sup>2</sup> (104B) 8-16ft <sup>2</sup> (104)	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-108</b>						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, corridor N1-101</b>						
Floor	12" X12" floor tile (off-white w/ light & dark tan mottles)	1400 ft <sup>2</sup>	N/A	1-224T	N/A	None detected
	Floor tile mastic	1400 ft <sup>2</sup>	N/A	1-224M	N/A	<b>8% Chrysotile</b>
	9" X 9" floor tile (by 104B)	6-8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above E ceiling	Pipe insulation in deck - Removed	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-96A</b>						
Floor	12" X 12" floor tile(over hard tile)	160 ft <sup>2</sup>	N/A	1-225T	N/A	None detected
	Floor tile mastic	160 ft <sup>2</sup>	N/A	1-225M	N/A	None detected
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-96</b>						
Floor	12" X12" floor tile (over hard tile)	50 ft <sup>2</sup>	N/A	N/A	1-225T	None detected
	Floor tile mastic	50 ft <sup>2</sup>	N/A	N/A	1-225M	None detected



**Building 1, Floor I - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room N1-97</b>						
Floor	12" X 12" floor tile (over hard tile)	160 ft <sup>2</sup>	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	1-225M	None detected
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-98</b>						
Floor	12" X12" floor tile (over hard tile)	160 ft <sup>2</sup>	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	1-225M	None detected
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, rooms N1-105A and N1-105</b>						
Floor	12" X 12" floor tile	160 ft <sup>2</sup> /area	N/A	N/A	1-225T	None detected
	Floor tile mastic	160 ft <sup>2</sup> /area	N/A	N/A	1-225M	None detected
	9" X 9" floor tile (under 12" X 12" )	160 ft <sup>2</sup> /area	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	160 ft <sup>2</sup> /area	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (N1-105 missing front panels)	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>1<sup>st</sup> Floor, N wing, room N1-109</b>						
Floor	12" X12" floor tile (tan w/ white & dark tan mottles) - Removed	300 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	300 ft <sup>3</sup>	N/A	N/A	N/A	N/A



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tiles	N/A	N/A	N/A	Previously tested	<1%
Above ceiling tile (N wall)	Pipe insulation	3 LF	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (front missing)	16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Comments: The front of the panels have been removed. The rear panes could not be observed at the time of this inspection and could be present.						
<b>1<sup>st</sup> Floor, N wing, room N1-110</b>						
Floor	12" X12" floor tiles - Removed	150 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	150 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, N wing, rooms N1-111, N1-112, N1-113, N1-114, N1-115, N1-116, N1-119</b>						
Floor	12" X 12" floor tile (yellow/orange) - Removed	180 ft <sup>2</sup>	N/A	N/A	8-039	N/A
	Floor tile mastic - Removed	180 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup> / Room	Damaged	N/A	N/A	<b>Assumed</b>
Chases	Pipe insulation - Assume still there	N/A	N/A	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

1 <sup>st</sup> Floor, N wing, room N1-120						
Floor	12" X 12" floor tile - Removed	200 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	200 ft <sup>2</sup>	N/A	N/A	N/A	N/A
1 <sup>st</sup> Floor, N wing, rooms N1-121, N1-122, N1-123, and N1-124 - Removed						
Floor	12" X 12" floor tile	100 ft <sup>2</sup> /area 50 ft <sup>2</sup> N1-124	N/A	N/A	8-039	None detected
	Floor tile mastic	100 ft <sup>2</sup> /area 50 ft <sup>2</sup> N1-124	N/A	N/A	8-040	<b>2% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1 <sup>st</sup> Floor, N wing, room N1-125						
Floor	12" X 12" floor tile - Removed	200 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	200 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
1 <sup>st</sup> Floor, N wing, room N1-130						
Floor	12" X 12" floor tile - Removed	100 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	100 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, room N1-131</b>						
Floor	12" X 12" floor tile - Removed	50 ft <sup>2</sup>	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	50 ft <sup>2</sup>	N/A	N/A	N/A	N/A
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>st</sup> Floor, N wing, telephone closet (off room N 1-136) and N1-128</b>						
Floor	12" X 12" floor ( telephone closet)	9 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	9 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	12" X 12" floor tile(N1-128) - Removed	25 ft <sup>2</sup>	N/A	N/A	N/A	Assumed
	Floor tile mastic - Removed	25 ft <sup>2</sup>	N/A	N/A	N/A	Assumed
<b>1<sup>st</sup> Floor, N wing, room N1-32 – Not on prints or Field</b>						
Floor	Rug over tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile	160 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles (N wall)	Pipe insulation	5 LF	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>ST</sup> Floor, N wing, rooms N1-134, N1-135, N1-136 ( dental area)</b>						
Floor	Rug over concrete or terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock and joint material	N/A	N/A	1-189	N/A	None detected
Above ceiling tiles (wall by nurse' station)	Pipe insulation - Removed	N/A	N/A	N/A	N/A	N/A
<b>1<sup>ST</sup> Floor, halls (in dental areas)</b>						
Floor	12" X12" floor tile - Removed	N/A	N/A	N/A	N/A	N/A
	Floor tile mastic - Removed	N/A	N/A	N/A	N/A	N/A
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>1<sup>ST</sup> Floor, N wing, room N1-136A – Area not present</b>						
Floor	12" X 12" floor tile	320 ft <sup>2</sup>	N/A	N/A	8-039	None detected
	Floor tile mastic	320 ft <sup>2</sup>	N/A	N/A	8-040	<b>2% Chrysotile</b>
Walls	Sheetrock	N/A	N/A	1-189	N/A	None detected
Ceilings	2'X4' ceiling tile	N/A	N/A	N/A	N/A	<b>Non-suspect</b>
<b>1<sup>ST</sup> Floor, N wing, room N1-137</b>						
Floor	12" X 12" floor tile (white w/tan & dark tan mottles)	20 ft <sup>2</sup>	N/A	N/A	5-69	None detected
	Floor tile mastic	20ft <sup>2</sup>	N/A	N/A	5-70	<b>5% Chrysotile</b>





**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>1<sup>st</sup> Floor, N wing, rooms N1-143, N1-142, N1-141, N1-140, N1-139 and N1-138</b>						
Floor	Rug over terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster / sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Main Chapel and Sacristy</b>						
Floor of main chapel	Rug over concrete (main area) Altar – rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" Floor tile (purple w/ white/dark purple markings)	940 ft <sup>2</sup>	N/A	C-149	N/A	None detected
	Floor tile mastic	940 ft <sup>2</sup>	N/A	C-159	N/A	<b>2% Chrysotile</b>
Floor of Sacristy	9" X 9" Floor tile	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Sheetrock/joints	N/A	N/A	N/A	Previously tested	None detected
Ceiling	2' X 2' ceiling tile (tan, rough variegations w/foil backing)	N/A	N/A	N/A	N/A	Non-suspect
Sacristy Closet	Pipe insulation	30-40 ft	Significant damage	N/A	N/A	<b>Assumed</b>
<b>Eucharist Room (21-3)</b>						
Floor	Rug over wood underlayment over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock/ Joint	N/A	N/A	N/A	Previously tested	None detected
Ceilings	2' X 4' ceiling tile (off-white, crater- like worm markings)	N/A	Good	C-148	N/A	None detected



**Building 1, Floor I - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>S Office (21-4)</b>						
Floor	Rug over 9" X 9" floor tile	150 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Mastic					<b>Assumed</b>
Walls	Sheetrock/Joints	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (Not fire rated)	N/A	N/A	N/A	N/A	Non-suspect
<b>Hall to Chapel (21-13)</b>						
Floor	12" X 12" floor tile/carpet	N/A	N/A	N/A	N/A	Non-suspect, installed after 1981
Pipes	Pipe fitting insulation	1 fitting	Good	N/A	N/A	<b>Assumed</b>

**NOTE: No suspect asbestos-containing material were observed in rooms C1-17, C1-31, C1-43, C1-44, C1-45, C1-51, C1-52, C1-104, C1-56A, N1-133, N1-132, main hallway in dental areas, and crawlspace behind room C1-22 (mechanical room). The halls within the East wing have been recently renovated – no suspect asbestos-containing materials observed. The Dental Wing was completely renovated since 2005 Inspection**



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

1511 Route 22, Suite C24, Brewster, NY 10509  
Phone: 845.278.7710 Fax: 845.278.7750

**Project:** Main Building, 2<sup>nd</sup> Floor  
VA Medical Center  
Wilkes-Barre, PA

**Inspector(s):** James Reber  
Thomas Ferro  
**Date(s):** 2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
<b>2<sup>nd</sup> Floor, Corridor – center/east (service elevator side and small hall to Nuclear Medicine)</b>						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	1100 ft <sup>2</sup>	good	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	1100 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation – mastic and cork	>100 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-02 (No access – Assume materials still present)</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Metal/concrete	N/A	N/A	N/A	N/A	Non-suspect
NW Comer	Pipe insulation	2 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-3A and C2-3B</b>						
Floor	Composite/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>Small closet of NE corner of Liberty Hall, C2-21</b>						
Floor	12" X 12" floor tile	16 ft <sup>2</sup>	N/A	N/A	6-103	<b>Assumed</b>
	Floor tile mastic	16 ft <sup>2</sup>	N/A	N/A	6-104	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, room C2-03</b>						
Floor	12" x 12" floor tile (light green w/ white & dark green mottles)	160 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	160 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-04</b>						
Floor	12" X 12" floor tile – replaced w/carpet					N/A
	Floor tile mastic –replaced w/carpet					N/A
Walls	Paneling over plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (white w/worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
In walls	Brown tissue paper- like material	N/A	N/A	2-116	N/A	None detected
On walls	Plaster (light/soft)	N/A	N/A	2-117	N/A	None detected
Comment: Pipe insulation may be in chase						



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-05</b>						
Floor	12" X 12" floor tile(light green w/white & dark green mottles)	168 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	168 ft <sup>2</sup>	N/A	V	7-59	<b>10% Chrysotile</b>
Walls	Tile/plaster/paneling	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off white w/ pinhole perforations & crater worm markings)	N/A	N/A	2-120	N/A	None detected
	2' X 4' ceiling tile (off-white w/pinholes & pockmarks)	N/A	N/A	N/A	2-123	None detected
<b>2<sup>nd</sup> Floor, room C2-05A</b>						
Floor	12" X 12" floor tile (off –white w/ white & brown streaks)	332 ft <sup>2</sup>	N/A	2-118	N/A	<b>&lt;1% Chrysotile</b>
	Floor tile mastic	332 ft <sup>2</sup>	N/A	2-119	N/A	<b>5% Chrysotile</b>
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation (aircell)	35-40 LF	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-05B</b>						
Floor	12" X12" floor tile (white w/brown streaks)	192 ft <sup>2</sup>	N/A	N/A	6-103	<b>5% Chrysotile</b>
	Floor tile mastic	192 ft <sup>2</sup>	N/A	N/A	6-104	<b>5% Chrysotile</b>
Walls	Sheetrock joint material	N/A	N/A	2-118	N/A	None detected
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above ceiling tile	Pipe insulation	28 LF	Good	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, hall by rooms C2-05A and 2-130</b>						
Floor	12" X12' floor tile (light green w/white & dark green mottles)	385 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	385 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above ceiling tile	Pipe insulation	<10 LF	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-06</b>						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	198 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
Univents	Transite Panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>Comment: Pipe insulation in chase - NE</b>						
<b>2<sup>nd</sup> Floor, rooms C2-07 &amp; C2-08</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" Floor tile	144 ft <sup>2</sup> / area	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	144 ft <sup>2</sup> / area	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tile( pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Above plaster ceiling (room C2-08 & C2-07)	Pipe insulation	30 – 35 LF	Significant damage	N/A	N/A	<b>Assumed</b>

<b>C2-09 and C2-10 – Probable asbestos pipe insulation in walls.</b>						
<b>C2-11 (corridor) – 12" X 12" green floor tile (7-58: 15% Chrysotile) and mastic (7-59: 10% Chrysotile) – 300 ft<sup>2</sup> - Good</b>						
<b>2<sup>nd</sup> Floor, Liberty Hall, room C2-14</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ sparse pinhole perforations & worm markings)	3500 ft <sup>2</sup>	N/A	2-121	N/A	<b>5% Chrysotile</b>
Above ceiling tile (N wall)	Pipe insulation (black mastic over cork)	N/A	Good	N/A	6-96	<b>8% Chrysotile</b>
	Pipe insulation (aircell)	N/A	Good	N/A	N/A	<b>Assumed</b>
Comment: Cannot check above ceiling tiles because it will disturb ACM						
<b>2<sup>nd</sup> Floor, room C2-13 (Credit Union) and C2-12</b>						
Floor	Rug over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	Previously tested	<b>&lt;1%</b>
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Vertical chase	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, rooms C2-14B, C2-14C, C2-14D, C2-14E, and C2-14F</b>						
Floor	Rug over concrete/ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-15</b>						
Floor	Rig over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	128 ft <sup>2</sup>	N/A	N/A	2-123	None detected
Above ceiling tile (over N wall)	Pipe insulation	4 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-16</b>						
Floor	Rug over ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 4' ceiling tile (pinhole perforations & worm markings)	144 ft <sup>2</sup>	N/A	N/A	2-123	None detected
Above ceiling tile (N side)	Pipe insulation	10 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-17, C2-18, C2-19 (C2-19 not found)</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	Non-suspect
Above ceiling and in chase( has cork pipe aircell)	Pipe insulation (aircell, mastic cork pipe)	>50 LF aircell >40 LF cork	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, pipe chase by C2-22 (electrical closet) (Room was not found)</b>						
Pipe	Pipe insulation (black mastic over cork)	3 LF	N/A	N/A	6-96	<b>8% Chrysotile</b>





**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-22</b>						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (tan w/white & dark tan mottles) – bathroom	40 ft <sup>2</sup>	N/A	N/A	8-039	None detected
	Floor tile mastic – bathroom	40 ft <sup>2</sup>	Good	N/A	8-040	<b>2% Chrysotile</b>
Ceilings	2' X4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, room C2-23</b>						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile (pinhole perforations w/ worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	24-48 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above ceiling tile	Pipe insulation (aircell)	16 LF	Good	N/A	N/A	<b>Assumed</b>
	Pipe insulation (black mastic over cork and MAG)	12 LF	Damaged	N/A	6-96	<b>8% Chrysotile</b>
<b>Threshold of C2-24 and C2-25 – 3 ft<sup>2</sup> - 12" X 12" Floor tile (blue green) and floor tile mastic.</b>						
<b>2<sup>nd</sup> Floor, room C2-24</b>						
Floor	Terrazzo tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile /plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tile (off-white w/perforations & worm markings)	648 ft <sup>2</sup>	N/A	N/A	2-128	None detected
Univents	Transite panels	40 – 80 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above ceiling and in chase	Pipe insulation	>20 LF	Good	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-25</b>						
Floor	Rug 12" X 12' pads (brown)	258 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
	Mastic	258 ft <sup>2</sup>	N/A	N/A	N/A	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
<b>2<sup>nd</sup> Floor, room C2-27A Mechanical</b>						
Pipes	Pipe insulation (black mastic over cork)	12 LF	Damaged	N/A	6-96	<b>8% Chrysotile</b>
<b>2<sup>nd</sup> Floor, room C2-28</b>						
Floor	Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile/plaster	Pipe insulation	25-30 LF	Good	N/A	N/A	<b>Assumed</b>
Univent	Transite panels (front missing)	8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, rooms C2-29 and C2-30</b>						
Floor	12"X 12" floor tile under rug (room C2-29 & C2-30)	420 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic (room C2-29)	420 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64 ft <sup>2</sup> /area	Damaged	N/A	N/A	<b>Assumed</b>
Above plaster in C2-29	Pipe insulation	16-20 LF	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, rooms C2-33A</b>						
Floor	12" X 12" floor tile – new	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' –new	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-30A</b>						
Floor	Rug over 12" X 12" floor tile/mastic	N/A	N/A	N/A	N/A	<b>&gt;1%</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> floor, room C2-31</b>						
Floor	Rug over floor tile	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white)	880 ft <sup>2</sup>	N/A	2-131	7-59	<b>5% Chrysotile</b>
	Floor tile mastic	880 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Wood paneling	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ perforations & worm markings)	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	24-48 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-33</b>						
Floor	<del>Rug over floor tile</del> No rug	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (off-white)	120 ft <sup>2</sup>	Good	2-132	N/A	<b>3% Chrysotile</b>
	Floor tile mastic	120 ft <sup>2</sup>	N/A	2-133	N/A	<b>3% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	20 – 40 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
E Wall	Pipe insulation	8 linear feet	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> floor, Room C2-33B through C2-43</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, room C2-43A – No suspect material</b>						



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, C2-44</b>						
Floor	Terrazzo Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile 9pinhole perforations & worn markings	N/A	N/A	N/A	2-123	None detected
<b>2<sup>nd</sup> Floor, hall by service elevator</b>						
Floor	12' X 12" floor tile (light green W/ white & dark green mottles)	200 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor mastic	200 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Brick/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
<b>Pipe insulation in chase behind elevator #2 – 15LF - Damaged</b>						
<b>2<sup>nd</sup> Floor, room C2-46 (Electrical closet)</b>						
Pipe	Pipe insulation (black mastic over cork)	12 LF	Good	N/A	6-96	<b>8% Chrysotile</b>
Pipe	Pipe/fitting insulation on fiberglass lines	4 fittings	Good	N/A	N/A	<b>Assumed</b>
<b>C2-106A and B, Pipe Room to N of 106B, and C2-107 – No exposed suspect asbestos containing materials observed.</b>						
<b>2<sup>nd</sup> Floor, room C2-47</b>						
Floor	12" X 12" floor tile (chocolate w/white & dk brown marble effect)	120 ft <sup>2</sup>	Good	N/A	7-86	None detected
	Floor tile mastic	120 ft <sup>2</sup>	N/A	N/A	7-87	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	12-24 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-118 and C2-121 (Library area)</b>						
Floor	Rug over	N/A	N/A	N/A		Non-suspect
	Mastic	N/A	N/A		2-112	None detected
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32-64ft <sup>2</sup> (C2-118) 56-112 ft <sup>2</sup> (C2-121)	Damaged	N/A	N/A	<b>Assumed</b>
<b>C2-129 and C2-130 – No exposed suspect asbestos materials observed. (Not found)</b>						
<b>Recreation Room</b>						
Floor	12" X 12" floor tile (off-white with brown mottles)	2000 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Mastic	2000 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, N wing, room N2-48 ( Labeled N2-49A on drawings)</b>						
Floor	12" X 12" floor tile (green mottles) Not there – newer 12" X 12"	180-200 ft <sup>2</sup>	N/A	N/A		
	Mastic	180-200 ft <sup>2</sup>	N/A	N/A		
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	12-24 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above ceiling tiles	Pipe insulation (aircell) – removed					



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room N2-49</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	36 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Utility room off C49 9 (N2-49B)	Pipe insulation (aircell)	10 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> floor, N wing, room N2-50</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock joint material/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels (front panels missing)	20 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
SW Chase	Pipe insulation	>20 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, N2-48A – Turned into mechanical room.</b>						
Floor	12" X 12" floor tile—green mottled) Removed					
	Mastic-Removed					
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Pipes in N wall	Pipe insulation/fitting	12 LF	Significant damage			<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-53</b>						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	40 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Chase – NE corner	Pipe insulation	>12 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, room N2-55 &amp; electrical room</b>						
Floor	Ceramic tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, N wing, room N2-56 (Electrical room)</b>						
Floor	Concrete/metal	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Vertical Chase	Pipe insulation 9black mastic over cork)	12 LF	Good	N/A	6-96	<b>8% Chrysotile</b>
Vertical Chase	Duct insulation (black mastic over cork)	100 ft <sup>2</sup>	Good	N/A	6-96	<b>8% Chrysotile</b>
<b>2<sup>nd</sup> floor, N wing, room N2-58</b>						
Floor	12" X 12" and 2' X 2'	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>





**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-60 – No exposed suspect asbestos materials observed.</b>						
<b>2<sup>nd</sup> Floor, N wing, room N2-59</b>						
Floor	12" X 12" Floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	32 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
<b>2<sup>nd</sup> Floor, N wing, rooms N2-64 and N2-64A</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings) – N2-64	N/A	N/A	N/A	2-123	None detected
	2' X 4' ceiling tile – N2-62	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe fitting - Removed	1	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (front panels missing)	36 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, rooms N2-66 and bathroom N2-67</b>						
Bathroom - in chases	Pipe insulation	>40 LF	Significant damage	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (N2-67)	8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-68</b>						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	250-300 ft <sup>2</sup>	N/A	N/A	8-039	None detected
	Floor tile mastic	250-300 ft <sup>2</sup>	N/A	N/A	8-040	<b>2% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
NE Corner chase	Pipe insulation – Same chase as N2-70	10-20 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, room N2-70</b>						
Floor	12" X 12" floor tile (tan w/white & dark tan mottles)	36 ft <sup>2</sup>	good	N/A	8-039	None detected
	Floor tile mastic	36 ft <sup>2</sup>	N/A	N/A	8-040	<b>2% Chrysotile</b>
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
S wall	Pipe insulation	10-20 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, room N2-71</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						



**Building 1, Floor 2 - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-74</b>						
Floor	Ceramic tile	N/A	N/A	N/A	8-039	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels ( front panels missing)	8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Above ceiling & in chase	Pipe insulation	45 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> floor, N wing, room N2-75</b>						
Floor	12" X 12' floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 44' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	32 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Over ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
<b>2<sup>nd</sup> Floor, N wing, bathroom at E end of radiology hall (Labeled N2-66)</b>						
Floor	12" X 12" floor tile (tan w/white and dk tan mottles) –Removed Non-suspect concrete					
	Floor tile mastic - Removed					
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2" X 2' ceiling tile (off-white w/pinhole perforations & small crater)	36 ft <sup>2</sup>	Good	2-127	N/A	None detected
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A



**Building 1, Floor 2 - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-77 and N2-77A</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	Non-suspect
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
In walls	Pipe insulation (Assume chases)	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, rooms N2-79 and N2-80</b>						
Floor	12" X 12" floor tile (light green w/white & dk green mottles)	320 ft <sup>2</sup>	Good	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	320 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing)	24 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Chase in N2-79	Pipe insulation	20-30 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, room N2-83A</b>						
Floor	12" X 12' floor tile(light green w/white & dark green mottles)	240 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	240 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster/sheetrock joint material	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

Ceilings	2'X4' ceiling tile (pinhole perforations & worm markings)	N/A	N/A	N/A	2-123	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	32 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
<b>2<sup>nd</sup> Floor, N wing, rooms N2-84 and N2-84A</b>						
Floor	12" X 12" floor tile	300 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	N/A	7-59	<b>10 % Chrysotile</b>
Ceilings	2' X 4' ceiling tile (pinhole perforation & worm markings)	N/A	N/A	N/A	2-123	None detected
Univents	Transite panels	8 ft <sup>2</sup> (N2-84) 16 ft <sup>2</sup> (N2-84A)	N/A	N/A	N/A	<b>Assumed</b>
Above ceiling tile	Duct insulation (black mastic over cork)	7 LF	N/A	N/A	6-96	<b>8%Chrysotile</b>
Chase in N2-84	Pipe insulation	>40 LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, main hall (radiology area)</b>						
Floor	12" X 12" floor tile (light green w/white and dk green mottles)	900 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	900 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-85 (files)</b>						
Floor-most of floor tiles in this room are new	12" X 12" floor tile (chocolate w/white & dk brown marble effect)	126 ft <sup>2</sup>	N/A	N/A	7-87T	None Detected
	Floor tile mastic	126 ft <sup>2</sup>	N/A	N/A	7-87M	<b>5% Chrysotile</b>
Walls	Plaster/sheetrock/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels (front panels missing on some, present on others)	64-100 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
	Pipe insulation	8 LF	Damaged	N/A	N/A	<b>Assumed</b>
Above ceiling tile	Duct insulation – removed	N/A	N/A	N/A	N/A	N/A
<b>2<sup>nd</sup> Floor, N wing, room N2-95 and N2-96 – Newly renovated – no suspect asbestos materials observed</b>						
<b>2<sup>nd</sup> Floor, N wing, room N2-97A and N2-97B</b>						
Floor	12" X 12" floor tile (green with mottles)	400 ft <sup>2</sup> (97A) 220 ft <sup>2</sup> (97B)	Good	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	400 ft <sup>2</sup> (97A) 220 ft <sup>2</sup> (97B)	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	36-72ft <sup>2</sup> (97A) 24-48ft <sup>2</sup> (97B)	Damaged	N/A	N/A	<b>Assumed</b>
NW Chase in 97A	Pipe insulation	>30 LF	N/A	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, N wing, room N2-98 and N2-99</b>						
Floor	9" x 9" floor tile (brown w/white & burnt sienna) (N2-98 only)	175 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	175 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above ceiling tile	Pipe insulation (aircell)	25 LF	Good	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, N wing, room N2-100 and N2-101</b>						
Floor	9" X 9" floor tile (brown w/white marks and burnt sienna) - N2-101 only	175 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	175 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Assume pipes above plaster ceiling – >30 LF						



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, C-102, C2-103, C2-104, C2-105, C-105A, C2-105B and C2-106</b>						
Floor – All floor tiles and mastic in these rooms are either new or tested negative for asbestos content	12" X 12" floor tile 9off-white w/blue mottles) –C2-106	N/A	N/A	2-129	N/A	<b>&lt;1% Chrysotile</b>
	Floor tile mastic	N/A	N/A	2-130	N/A	None detected
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (pinhole perforations & worm markings) – C2-102, C2-103 & C2-104	525 ft <sup>2</sup>	N/A	N/A	2-123	None detected
	2' X 4' ceiling tile (off-white w/pinhole perforations & craters)– C2-105 & adjoining room to S	400 ft <sup>2</sup>	N/A	2-128	N/A	None detected
Above ceiling and in chases	Pipe insulation 4 LF above ceiling tiles, rest in chase	> 40 LF	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	88 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
<b>2<sup>nd</sup> Floor, room C2-108</b>						
Univents	Transite panels	8 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Above ceiling & in chases	Pipe insulation -	15 LF above plaster, 20-30 LF in chases	Good	N/A	N/A	<b>Assumed</b>
Comments: The front transite panels have been removed. The rear panels could not be observed at the time of this inspection and could be present.						
<b>2<sup>nd</sup> Floor, room C2-109</b>						
Floor	12" X 12" floor tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect





**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Center chase	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-112</b>						
Floor	12" X 12' floor tile (Chocolate w/white/brown & gray marbling )	180 ft <sup>2</sup>	N/A	N/A	7-86	None detected
	Floor tile mastic	180 ft <sup>2</sup>	N/A	N/A	7-87	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, room C2-113</b>						
Floor	Rig over concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>2<sup>nd</sup> Floor, room C2-115 (Part of Library)</b>						
Floor	Rug over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	N/A	N/A	N/A	2-112	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x2' ceiling tile (rough faced0	1224 ft <sup>2</sup>	N/A	N/A	2-228	None detected
Above ceiling tile	Pipe insulation	20 LF	Damaged ends exposed	N/A	N/A	<b>Assumed</b>



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-116 ( Library)</b>						
Floor	Rig over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	308 ft <sup>2</sup>	N/A	2-112	N/A	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile (rough faced)	N/A	N/A	2-228	N/A	None detected
NW corner chase	Pipe insulation – can't see from above ceiling	8 LF	N/A	N/A	N/A	<b>Assumed</b>
Above ceiling and in south/center chase	Pipe insulation - can't see from above ceiling	>4LF	N/A	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-117</b>						
Floor	Rug over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	168 ft <sup>2</sup>	N/A	N/A	2-112	None detected
	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile (rough faced)	N/A	N/A	N/A	2-288	None detected
Univents	Transite panels	32-64 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, electrical closet by stair #1</b>						
Pipe riser	Pipe insulation (black mastic over cork)	12 LF	N/A	2-115	N/A	<b>5% Chrysotile</b>



**Building 1, Floor 2 - Specific Survey Findings  
Project No. VAMC: 10013.00-IN**

<b>2<sup>nd</sup> Floor, room C2-119</b>						
Floor	Rig over black mastic	N/A	N/A	N/A	N/A	Non-suspect
	Mastic	N/A	N/A	N/A	2-112	None detected
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' x 2' ceiling tile (rough faced)	288 ft <sup>2</sup>	N/A	N/A	2-228	None detected
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, room C2-120</b>						
Floor	12" X 12' floor tile(cream w/white & olive mottles)	300-400 ft <sup>2</sup>	N/A	2-113	N/A	<b>&lt;1% Chrysotile</b>
	Floor tile mastic	300-400 ft <sup>2</sup>	N/A	2-114	N/A	<b>3% Chrysotile</b>
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	408 ft <sup>2</sup>	N/A	N/A	2-228	None detected
Univents	Transite panels	64 - 128 ft <sup>2</sup>	Significant damage	N/A	N/A	<b>Assumed</b>
<b>2<sup>nd</sup> Floor, main hall</b>						
Floor	12' X 12" floor tile (light green)	1600 ft <sup>2</sup>	Good	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	1600 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 2' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect



**Building 1, Floor 2 - Specific Survey Findings**  
**Project No. VAMC: 10013.00-IN**

2 <sup>nd</sup> Floor, rooms 2-130 and 2-129						
Floor	Composite	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile (off-white w/ pinhole & pockmarks)	96 ft <sup>2</sup> /area	N/A	2-123	N/A	None detected

NOTE : No suspect asbestos-containing materials were observed in the following areas N2-73, N2-74, C2-43A, C2-106A and C2-106B.



**Basement - Building 17 (Warehouse) & Building 1, Specific Survey Findings**  
Project No. 05-033-1

1511 Route 22, Suite C24, Brewster, NY 10509  
Phone: 845.278.7710 Fax: 845.278.7750

**Project: Basement – Building 17 (Warehouse) and Building 1**

VA Medical Center  
1111 East End Blvd.  
Wilkes-Barre, PA 18711

**Inspector(s):** James Reber

**Date(s):** Thomas Ferro  
2/2010-3/2010

LOCATION	MATERIAL	QUANTITY	CONDITION	SAMPLE #	HOMOGENEOUS WITH SAMPLE #	ASBESTOS CONTENT
<b>Basement, general storage area – Building 17</b>						
Floor	12" X 12" Floor tile (brown/white with gray/ dark brown marble effect (Removed – Floor is Concrete)	3750 ft <sup>2</sup>	N/A	N/A	7-86	None detected (Removed – Floor is Concrete)
	Floor tile mastic (Removed – Floor is Concrete)	3750 ft <sup>2</sup>	N/A	N/A	7-87	5% Chrysotile (Removed – Floor is Concrete)
Walls	Brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Pipes	Mudded Pipe Fittings on fiberglass steam and cold water line near entrance	4 LF	Good	N/A	N/A	<b>Assumed</b>
<b>Basement, BW-103 – Building 17</b>						
Floor	12" X 12" Floor tile (brown/white with gray/ dark brown marble effect) (Removed)	120 ft <sup>2</sup>	N/A	N/A	7-86	None detected (Removed)
	Floor mastic (Removed)	144 ft <sup>2</sup>	N/A	N/A	7-87	5% Chrysotile (Removed)
Walls	Brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect

**VA Medical Center, Building No. 17 (Warehouse) & Building 1**

Adelaide Environmental Health Services, Inc. – Project No. 05-033-01



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, BW-104 – Building 17</b>						
Floor	12" X 12" Floor tile (brown/white with gray/ dark brown marble effect) (Removed)	120 ft <sup>2</sup>	N/A	N/A	7-86	None detected (Removed)
	Floor tile mastic (Removed)	120 ft <sup>2</sup>	N/A	N/A	7-87	5% Chrysotile (Removed)
Walls	Brick	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, WH004-17 – Building 17</b>						
Floor	12" X 12" Floor tile (brown/white with gray/dark brown marble effect) (Removed)	450 ft <sup>2</sup>	N/A	N/A	7-86	None detected (Removed)
	Floor tile mastic (Removed)	450 ft <sup>2</sup>	N/A	N/A	7-87	5% Chrysotile (Removed)
Walls	Brick/Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, WH005-17 – Building 17</b>						
Floor	12" X 12" Floor tile (Blue, new and less than 10 years old)	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile mastic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Block	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-151</b>						
Floor	12" X 12" Floor tile	400 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	400 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, store, CB-150</b>						
Floor	9" X9" Floor tile	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation- above ceiling tile and imbedded in N wall	8-10	Good	N/A	N/A	<b>Assumed</b>
<b>Basement, Office and related rooms (CB-146, CB-148 &amp; CB-149)</b>						
Floor	12" X 12" Floor tile (new)	N/A	N/A	N/A	N/A	Non-suspect
	Floor tile mastic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Wood paneling over plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (CB-146)	12 linear feet	Good	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, Main store area (CB-01 &amp; CB-01A)</b>						
Floor	12" X 12" Floor tile (top layer) /mastic – new	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" Floor tile (bottom layer) light green with white/dark green mottles – extends under at least part of the top (see floor traps in SW corner)	1000 SF	Good	N/A	7-58	<b>15% Chrysotile</b>
	Mastic	1000 SF	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Wood	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, CB-12 (post office)</b>						
Floor	9" X 9" Floor tile	200 ft <sup>2</sup>	N/A	03-T-5	N/A	<b>5% Chrysotile</b>
	Floor tile mastic	200 ft <sup>2</sup>	N/A	04-T-5	N/A	None detected
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe Insulation (aircell and black mastic over cork)	5 LF (aircell) 4 LF (cork)	Damaged	N/A	N/A	<b>Assumed</b>
<b>Basement, Kitchen main area – CB-78</b>						
Floor	Ceramic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Ceramic	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Over ceiling	Pipe insulation (black mastic over cork)	10 LF	Good	N/A	N/A	<b>Assumed</b>





**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, Kitchen area – CB 77</b>						
Floor	12" X 12" floor tile(off-white w/brown and white streaks)	115 ft <sup>2</sup>	N/A	N/A	1-98	<b>5% Chrysotile</b>
	Floor tile mastic	115 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4" ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, CB-72</b>						
Floor	12" X 12" floor tile (off white w/brown streaks)	300 ft <sup>2</sup>	N/A	01-T-5	N/A	<b>3% Chrysotile</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	02-M-5	N/A	<1% Chrysotile
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, CB-76</b>						
Floor	12" X 12" floor tile (off white w/ white and brown streaks)	400 ft <sup>2</sup>	N/A	N/A	1-98	<b>5% Chrysotile</b>
	Floor tile mastic	400 ft <sup>2</sup>	N/A	N/A		<b>Assumed</b>
Walls	Plaster/Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tile	Pipe insulation (black mastic over cork)	25 LF	Good	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-73</b>						
Floor	12" X 12" floor tile (off white w/ white and brown streaks)	725 ft <sup>2</sup>	N/A	N/A	1-98	<b>5% Chrysotile</b>
	Floor tile mastic	725 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/tile/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles	Pipe insulation (black mastic over cork)	>40 linear feet	Good	N/A	N/A	<b>Assumed</b>
<b>Basement, CB-64</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Note: Spray fireproofing above ceiling tile was tested in other areas and does not contain asbestos.						
<b>Basement, room CB-60A, CB-62, CB-62A – No exposed suspect materials observed.</b>						
<b>CB-56 – No exposed suspect materials observed.</b>						
<b>Basement, CB-59 and CB-59A</b>						
Floor	Rug over floor tiles	375 SF (CB-59) 221 SF (CB-59A)	Good	N/A	N/A	<b>Assumed</b>
<b>Basement, Room CB-55</b>						
Floor	12" X 12" floor tile (Tan brown mottles)	165 ft <sup>2</sup>	N/A	N/A	Previously Tested	<1% Chrysotile
	Floor tile mastic	165 ft <sup>2</sup>	N/A	N/A	Previously Tested Positive	<b>&gt;1% Chrysotile</b>
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, Rooms CB-66, 67 – Non exposed suspect material observed</b>						
<b>Basement, Room CB-51A</b>						
Floor	9x9 Floor Tiles (North side and threshold only)	10 SF	Significant Damage	N/A	N/A	<b>Assumed</b>
<b>Basement Room CB-48 (corridor)</b>						
Floor	12" X 12" floor tile (green/mottles) (Abated by Canteen Section ~618 SF)	ft <sup>2</sup>	N/A	N/A	7-58	15% Chrysotile (Removed From Canteen Area)
	Floor tile mastic (Abated by Canteen Section ~618SF)	ft <sup>2</sup>	N/A	N/A	7-59	10% Chrysotile (Removed From Canteen Area)
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Over ceiling tile	Pipe insulation (Removed above canteen area)	N/A	N/A	N/A	N/A	Assumed (Removed above canteen area)
<b>Basement, CB-58</b>						
Floor	12" X 12" floor tile (rug over top)	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	300 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, CB-57</b>						
Floor	Rug over leveling compound, possible tile underneath	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-60</b>						
Floor	Rug	160 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
	Ceramic Tiles under rug	160 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
	Joint Material	N/A	N/A	N/A	1-199	Non-suspect
Ceiling	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, kitchen area, dishwashing section and Corridor (CB-80 and 80E)</b>						
Above ceiling	Pipe insulation (black mastic on cork)	45 LF (CB-80) 15 LF (CB-80E)	Good	N/A	6-96	<b>8% Chrysotile</b>
<b>Basement, CB-52, 53 (cooler) – Possible insulation in walls, ceilings, floors</b>						
<b>Basement, CB-23</b>						
Floor	12" X 12" floor tile (light green w/white and dark green mottles)	240 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	240 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles (Removed – replaced with new 2'x4')	N/A	N/A	B-144	N/A	5% Chrysotile (Removed – replaced with new 2'x4' – Non-suspect)
Above ceiling	Pipe insulation (some damaged material lying on top of ceiling tiles in SW corner) (*debris gone – ceiling tiles are new and pipes remain)	80-90 LF	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	32-64 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-25</b>						
Floor	12" X 12" floor tile (light green w/white and dark green mottles)	315 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	315 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Univents	Transite panels	36-72 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>Basement, CB-26</b> (Door from Hallway sealed and entry is through CB-25 which is accessed from CB-23)						
Floor	9" X 9" floor tile (dark brown w/white and pinkish mark)	162 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	162 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Pipes	Blocks under strap hangers & pipe & pipe fittings	6/10 linear ft	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>Basement, CB-28</b>						
Floor	12" X 12" floor tile (light green w/white and dark green mottles)	240 ft <sup>2</sup>	N/A	N/A	7-58	<b>15% Chrysotile</b>
	Floor tile mastic	240 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	240 ft <sup>2</sup>	N/A	4/13 -01	N/A	None detected
Univents	Transite panels (front panels gone)	20 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, janitorial storage - across from EB-29, plus side rooms (Room Label on Drawings as EB-44,38H and 48B)</b>						
Floor	12" X 12" floor tile (white with blue marks)	1000 ft <sup>2</sup>	N/A	4/13-02	N/A	None detected
	Floor tile mastic	315 ft <sup>2</sup>	N/A	4/13-03	N/A	<1% Chrysotile
Walls	Sheet rock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings 2' X 4' ceiling	N/A	N/A	N/A	N/A	N/A	Non-suspect
Above tiles in main area	Pipe insulation (Removed)	> 100 linear ft (removed)	N/A	N/A	N/A	Assumed (Removed)
<b>Basement, EB-41</b>						
Floor	12" X 12" floor tile (white w/blue marks)	250 ft <sup>2</sup>	N/A	N/A	4/13-02	None detected
	Floor tile mastic	162 ft <sup>2</sup>	N/A	N/A	4/13-03	<1% Chrysotile
Walls	Sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Chases	Pipe insulation (cant view in chase)	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement, EB-49 (corridor) **(Area not found in the field or on drawings for 2010 Inspection)**</b>						
Floor	12" X 12" floor tile (white w/blue marks)	N/A	N/A	N/A	4/13-02	None detected
	Floor tile mastic	N/A	N/A	N/A	4/13-03	<1% Chrysotile
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2'X4' ceiling tiles	240 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (front panels gone)	32-64 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement, EB-39A through 39F, and corridor (EB-39) – all new – no exposed suspect materials observed.</b>						
<b>Basement, CB-8, CB-9, CB-11 and associated rooms – all new – no exposed suspect materials observed.</b>						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-14, CB-15 – Transite panels in univents – 32- 64 ft<sup>2</sup>. 2' X 4' ceiling tile in CB-14 – negative (sample #4/14 – 04)</b>						
<b>Basement, CB-16 and CB-16A, CB-18B, CB-18C, CB-18D</b>						
Floor	12" X 12" floor tile (tan w/dark tan and white spots)	250-300 ft <sup>2</sup> (16&A) ~ 200 ft <sup>2</sup> (18B,C,D)	N/A	4/14-01	N/A	None detected
	Mastic	250-300 ft <sup>2</sup> (16&A) ~ 200 ft <sup>2</sup> (18B,C,D)	N/A	4/14-02	N/A	<b>3% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling tiles (16, 16A and 18D)	Pipe insulation	60 LF(CB-16) 20 LF(CB-16A) 20 LF(CB-18D)	Good	N/A	N/A	<b>Assumed</b>
Univents (CB-16)	Transite panels	16-32 ft <sup>2</sup>	Significant Damage	N/A	N/A	<b>Assumed</b>
<b>Basement, CB-19 and CB-19A</b>						
Pipes	Pipe Insulation	8 LF(CB-19)	Good	N/A	N/A	<b>Assumed</b>
Above Plaster in CB-19A and in chase	Pipe Insulation	10 LF(above plaster) 20 LF(chase)	Significant Damage	N/A	N/A	<b>Assumed</b>
<b>**Note: Pipe insulation debris is present on plaster ceiling of CB-19A</b>						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-18, CB-18A</b>						
Floor	12" X 12" floor tile ( tan w/brown mottles	~550 ft <sup>2</sup>	N/A	N/A	Previously tested	<1%
	Floor mastic tile	~550 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Sheetrock/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	240 ft <sup>2</sup>	N/A	b-144	N/A	N/A
Above ceilings	Pipe insulation (Mag)	20 LF(CB-18) 40 LF(CB-18A)	Good	N/A	N/A	<b>Assumed</b>
<b>Basement, CB-20, CB-20A</b>						
Risers and at ceiling	Pipe insulation (Black mastic over cork)	>12 linear ft (CB-20) 5 linear ft (CB-20A)	Good	N/A	N/A	<b>Chrysotile 8%</b>
<b>Basement, CB-21 and CB-22</b>						
Floor	12" X 12" floor tile (green w/mottles) (CB-22 only)	215 ft <sup>2</sup>	N/A	N/A	7-58	<b>~15% Chrysotile</b>
	Floor tile mastic (CB-22 only)	215 ft <sup>2</sup>	N/A	N/A	7-59	<b>10% Chrysotile</b>
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceilings & in chases	Pipe insulation - ?	40 LF(CB-21) 60-80 LF(CB-22)	Good	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	8-16 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>





**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, EB-38B</b>						
Floor	12" X12" floor tile	~150 ft <sup>2</sup>	N/A	4/14-05	N/A	None detected
	Floor tile mastic	~150 ft <sup>2</sup>	N/A	4/14-06	N/A	None detected
Walls	Tile/plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	240 ft <sup>2</sup>	N/A	B-144	N/A	N/A
<b>Basement, CB-54 ( corridor)</b>						
Floor	12" X 12" floor tile (Removed – Concrete now)	~240 ft <sup>2</sup>	N/A	N/A	Previously tested	<1% (Removed – Concrete Now)
	Floor tile mastic (Removed – Concrete Now)	N/A	N/A	N/A	7-59	>1% (Removed – Concrete now)
Walls	Tile/Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement CB-54 (corridor) – Pipe insulation at N wall **Not found in 2010 Inspection – Area has been renovated</b>						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, Canteen/Cafeteria area- all new except observed or suspected pipe insulation (black mastic over cork, or other) over ceilings in the following areas:</b>						
CB-02	Pipe insulation (Cork Pipe)	~12 linear ft	Good	4/14-05	N/A	<b>8% Chrysotile</b>
CB-03	Pipe insulation (Mag)	12 LF (another 20 LF with Chase)	Good	4/14-06	N/A	<b>Assumed</b>
CB-03A	Pipe insulation (None Found)	?	N/A	N/A	N/A	Assumed (none found in 2010)
CB-04	Pipe insulation (Mag)	10 LF	Good	B-144	N/A	<b>Assumed</b>
CB -05	Pipe insulation (in concrete ceiling deck)	2 LF	N/A	N/A	N/A	<b>Assumed</b>
CB-48	Pipe insulation (all piping was fiberglass – area renovated and ACM removed)	>100 linear ft	N/A	N/A	N/A	Non-suspect
Univents in canteen (dining area)	Transite panels (front panels missing in CB-06A)	100 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, CB-10</b>						
Floor	12" x 12" floor tile (beigew/light brown mottles)	572 SF	Damage	8-036	N/A	None detected
	Floor tile mastic	572 SF	Damage	8-037	N/A	<b>5% Chrysotile</b>
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Southwest Corner	Two Large Fittings for old vacuum delivery tube system	10 SF	Good	N/A	N/A	<b>Assumed</b>
Above ceiling	Glue pucks and 1'x1' Ceiling Tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement, CB-13 and CB-153 (Corridor by Silver Elevators)</b>						
Floor	12" X 12" floor tile (beige w/yellow/orange mixed in)	3000 SF	N/A	N/A	Previously tested positive	<b>&gt;1%</b>
	Floor tile mastic	3000 SF	N/A	N/A	Previously tested positive	<b>&gt;1%</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceilings (Area Renovated)	Pipe insulation (Removed)	80-90	N/A	N/A	N/A	Assumed (Removed)
<b>Basement CB-18B – 2 suspect pipes at W wall</b>						
<b>Basement, Warehouse IV room at the end of hall leading to center court (Not found)</b>						
Floor	12" X 12" floor tile (tan w/white and brown marks)	336 ft <sup>2</sup>	N/A	N/A	B-141	ND
	Floor tile mastic	336 ft <sup>2</sup>	N/A	N/A	B-142	<1% Chrysotile
Walls	Plater/sheetrock	336 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	B143	ND



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement, EB-43</b>						
Wall Chase	Pipe insulation	>20 LF	Significant Damage	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, CB-51</b>						
Floor	12" X 12" floor tile (light grey w/white and dark grey mottles)	264 ft <sup>2</sup>	N/A	N/A	6-105	ND
	Floor tile mastic	264 ft <sup>2</sup>	N/A	N/A	6-106	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (Mag)	25-30 LF	Good	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, hall by CB-52 over loading dock area</b>						
Above ceiling	Pipe insulation (removed)	5ft (Removed)	N/A	N/A	N/A	Assumed (Removed)
	Cement fittings on fiberglass insulation (Removed)	2 each (Removed)	N/A	N/A	N/A	Assumed (Removed)
<b>Basement of main building, NB-98and NB-100</b>						
Floor	12" X 12" floor tile(white w/gray and olive streaks)	220 SF(both rooms)	Good	N/A	Previously tested positive	<b>&gt;1%</b>
	Floor tile mastic	220 SF(both rooms)	Good	N/A	Previously tested positive	<b>&gt;1%</b>
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceilings	Pipe insulation	80-100 lf	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	24-48 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>**Note: Room NB-100 has a chase exposed and some ceiling tiles removed; pipe insulation debris is in near floor of opened chase**Hazard**</b>						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-101</b>						
Floor	9" X 9" floor tile	180 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
	Floor mastic	180 ft <sup>2</sup>	Good	N/A	N/A	<b>Assumed</b>
Walls	Plaster/Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	180 ft <sup>2</sup>	N/A	N/A	2-121	<b>5% Chrysotile</b>
Above ceiling**	Pipe insulation**	60-100 linear feet**	N/A	N/A	N/A	<b>Assumed**</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>**Assume pipes above ceiling tile; ceiling tiles contain asbestos and will be disturbed if moved**</b>						
<b>Basement of main building, NB-102</b>						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	200 ft <sup>2</sup>	N/A	N/A	2-121	<b>5% Chrysotile</b>
Above ceiling**	Pipe insulation**	24-48**	N/A	N/A	N/A	<b>Assumed**</b>
Univents	Transite Panels	24-28 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>**Assume pipes above ceiling tile; ceiling tiles contain asbestos and will be disturbed if moved**</b>						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-104</b>						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	200 ft <sup>2</sup>	N/A	N/A	2-121	<b>5% Chrysotile</b>
Above ceiling	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>**Assume pipes above ceiling tile; ceiling tiles contain asbestos and will be disturbed if moved**</b>						
<b>Basement of main building, NB-105</b>						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceiling	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement of main building, NB-106</b>						
Floor	Ceramic Tile	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Chase	Pipe insulation (assume – No access to chase)	2-3 lf	N/A	N/A	N/A	<b>Assumed</b>
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
Above plaster ceiling	Pipe insulation (no access above plaster – assume)	N/A	N/A	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-107</b>						
Floor	12" X 12" floor tile (removed – replaced w/ new 12x12)	400 ft <sup>2</sup>	N/A	N/A	B-275	10% Chrysotile (Removed – replaced w/ new 12x12)
	Floor tile mastic (Removed)	240 ft <sup>2</sup>	N/A	N/A	B-276	5% Chrysotile (Removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non suspect
Ceilings	2' X 4' ceiling tiles (fiberglass)	240 ft <sup>2</sup>	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	40-80 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, NB-110B (Room 09)</b>						
Floor	12" X 12" floor tile ( off white w/gray and white mottles) (Removed – replaced w/ new 12x12)	200 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (removed – replaced w/ new 12x12)
	Floor tile mastic (removed)	200 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, room NB-110A (Room 8)</b>						
Floor	12" X 12" floor tile (off white w/ gray and white mottles) (Removed – replaced w/ new 12x12)	200 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (Removed – replaced w/ new 12x12)
	Floor tile mastic (Removed)	200 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (Removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' Ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-111 and NB-112</b>						
Floor	9" X 9" floor tile (white w/blue marks)	175 SF/each room	Good	N/A	N/A	<b>Assumed</b>
	Floor tile mastic	175 SF/each room	Good	N/A	N/A	<b>Assumed</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>
NB-112 - Ewall	Pipe insulation	N/A	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, NB-114</b>						
Floor	Terrazzo	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles – new	N/A	N/A	N/A	N/A	N/A
<b>Basement of main building, NB-116</b>						
Floor	Ceramic	240 ft <sup>2</sup>	N/A	N/A	7-58	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (Removed above ceiling but most likely still in walls; poly is left behind above ceiling)	80-100	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels	16-32 ft <sup>2</sup>	Damaged	N/A	N/A	<b>Assumed</b>





**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-117 (includes 2 rooms and small hall)</b>						
Floor	12" X 12" floor tile underneath carpet	250 ft <sup>2</sup>	N/A	N/A	B-275	<b>10% Chrysotile</b>
	Floor tile mastic	250 ft <sup>2</sup>	N/A	N/A	B-276	<b>5% Chrysotile</b>
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling (removed)	Pipe insulation (removed above ceiling tiles but still in walls)	50 LF	N/A	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (front panel missing)	16 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, electrical closet NB-97A</b>						
Floor/pipes	Tar on cork – Cork and mastic insulation is laying on floor and on tops of pipes in area (residue from previous removal) **Debris is no longer on floor but still found above pipes in area**	Debris	Significant Damage	N/A	6-96	<b>Assumed</b>
<b>Basement of main building, Main hall, north emergency room area (NB-108)</b>						
Floor	12" X 12" Floor tile (white w/tan mottles)	700 SF	N/A	N/A	0-036	<b>ND</b>
	Floor tile mastic	700 SF	N/A	N/A	8-037	<b>5% Chrysotile</b>
Walls	Fiberboard	N/A	N/A	N/A	B-279	N/A
<b>Basement of main building, NB-119 *(Room is combined with what was NB-117)</b>						
Floor	12" X 12" floor tile (light green w/white and dark green mottles) (No floor tile found under carpet in NB-119 area)	160-180 ft <sup>2</sup>	N/A	N/A	7-58	15% Chrysotile (Removed – Carpet on concrete)
	Floor tile mastic (removed)	160-180 ft <sup>2</sup>	N/A	N/A	7-59	10% Chrysotile (removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
In wall chase outside entry door	Pipe insulation	12 LF	Damaged	N/A	N/A	<b>Assumed</b>
Univents	Transite panels (front panels missing)	16 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, NB-122</b>						
Floor	12" X 12" floor tile (2 types) (Removed and replaced – carpet on concrete)	130 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (Removed and replaced with carpet on concrete)
	Floor tile mastic (Removed)	130 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
	Glued on ceiling tiles (removed)	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (Removed)	N/A	N/A	N/A	N/A	(Removed)
<b>Basement of main building, NB-123 and back room (NB-121)</b>						
Floor	12" X 12' floor tile (tan w/white and brown mottles) (Removed and replaced – carpet on concrete)	340 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (Removed and replaced – carpet on concrete)
	Floor tile mastic (Removed)	340 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1% (Removed)
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling (removed)	Pipe insulation- This pipe insulation can be seen running E over plaster ceilings in associated room and in NB-122 (removed)	N/A	N/A	N/A	N/A	Assumed (removed)



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, NB-128 / NB-124 suite (all rooms except 128A and B)</b>				<b>**Removed during Pharmacy Gut Renovation**</b>		
Floor	12" X 12" floor tile and mastic (off white w/tan mottles)	2500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Above ceiling	Pipe insulation	128j – 20ft	Significantly damaged	N/A	N/A	Assumed
		128h – 30ft	Good			
		128f – 40ft	Good			
		128e – 75ft	Good			
		128d – 25ft	Good			
		128c – 10ft	Good			
<b>Basement of main building, NB-128A / NB-128B (part of overall suite)</b>				<b>**Removed during Pharmacy Gut Renovation**</b>		
Floor	12" X 12" floor tile	Included in 2500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	Included in 2500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non suspect
Above ceiling	Duct insulation	240 ft <sup>2</sup>	Damaged	N/A	B-280	30% Chrysotile
	Pipe insulation	20 ft <sup>2</sup>	N/A	N/A	N/A	<b>Assumed</b>
<b>Basement of main building, hall for suite 128</b>				<b>**Removed during Pharmacy Gut Renovation**</b>		
Floor	12" X 12" floor tile	Included in 2500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	Included in 2500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (tar on cork)	30 lf	N/A	N/A	6-96	8% Chrysotile



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, admissions/reception area and 2 entrance foyers</b>			<b>**Removed during Pharmacy Gut Renovation**</b>			
Floor	12" X 12" floor tile	1500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
	Floor tile mastic	1500 ft <sup>2</sup>	N/A	N/A	Previously tested positive	>1%
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Above ceiling	Pipe insulation (tar over cork)	40 lf	N/A	N/A	6-96	8% Chrysotile
<b>Basement of main building, pharmacy area</b>			<b>**Removed during Pharmacy Gut Renovation**</b>			
Floor	12" X 12" floor tile (off white w/ gray and dark gray marbling effect) - applied after 1982	N/A	N/A	N/A	N/A	Non- suspect
	Floor tile mastic	N/A	N/A	N/A	N/A	Non-suspect
	12" X 12" floor tile (white w/brown streaks)	150 ft <sup>2</sup>	N/A	N/A	6-103	5% Chrysotile
	Floor tile mastic	150 ft <sup>2</sup>	N/A	N/A	6-104	5% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tile	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement of main building, 1D label:10A-1</b>			<b>**Removed during Pharmacy Gut Renovation**</b>			
Floor	Rug flooring – cannot lift rug	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plater/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
Comments: could not get rug up from floor to check tile beneath						



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement of main building, waiting room of pharmacy</b>		<b>**Removed during Pharmacy Gut Renovation**</b>				
Floor	12" X 12" floor tile (light tan w/white and dark tan mottles)	1500 ft <sup>2</sup>	N/A	N/A	8-039	ND
	Floor tile mastic	1500 ft <sup>2</sup>	N/A	N/A	8-040	2% Chrysotile
Walls	Plaster/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non- suspect
Univents	Transite panels	32-64 ft <sup>2</sup>	N/A	N/A	N/A	Assumed
<b>Basement of main building, bathroom near reception</b>		<b>**Removed during Pharmacy Gut Renovation**</b>				
Floor	Ceramic	N/A	N/A	N/A	N/A	Non-suspect
Walls	Plaster/tile	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement of main building, main hall – reception/admissions (NB-133/124)</b>		<b>**Removed during Pharmacy Gut Renovation**</b>				
Floor	12" X 12" floor tile ( tanw/ white and brown mottles)	N/A	N/A	N/A	5-69	ND
	Floor tile mastic	N/A	N/A	N/A	5-70	5% Chrysotile
Above ceiling tile	Pipe insulation	N/A	N/A	N/A	N/A	Assumed



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Basement north, records area – south section</b>			<b>**Removed during Pharmacy Gut Renovation**</b>			
Floor	12" x 12" floor tile (brown w/white and dark brown marks)	1040 ft <sup>2</sup>	N/A	N/A	B-275	10% Chrysotile
	Floor tile mastic	1040 ft <sup>2</sup>	N/A	N/A	B-276	5% Chrysotile
Walls	Cinderblock/sheetrock	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement of main building, record storage – north section</b>			<b>**Removed during Pharmacy Gut Renovation**</b>			
Floor	12" x 12" floor tile (white w/ gray marks)	500 ft <sup>2</sup>	N/A	N/A	B-277	ND
	Floor tile mastic	500 ft <sup>2</sup>	N/A	N/A	B-278	10% Chrysotile
	12" X 12" floor tile (light green w/ white and darker green mottles)	500 ft <sup>2</sup>	N/A	N/A	7-58	15% Chrysotile
	Floor tile mastic	500 ft <sup>2</sup>	N/A	N/A	7-59	10% Chrysotile
Ceiling	2' X 4' ceiling tiles	N/A	N/A	N/A	N/A	Non-suspect
<b>Basement of main building, canteen area electrical closet (CB-02)</b>						
Above ceiling	Pipe insulation (mastic on cork)	12 ft	Damaged	N/A	6-96	<b>8 % Chrysotile</b>
<b>Basement, Canteen Kitchen (CB-141)</b>						
Above Ceiling Tiles	Pipe Insulation and Insulation Debris	30-50 LF	Significant Damage	N/A	N/A	<b>Assumed</b>



**Building 17 (Warehouse) & Building 1, Specific Survey Findings  
Project No. 05-033-01**

<b>Sub Basement, confined space (steam pit) off stairwell 3 basement level</b>						
Floor	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Walls	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Ceilings	Concrete	N/A	N/A	N/A	N/A	Non-suspect
Comments: Chases looked into – no suspect materials as far as the eye can see.						

**NOTE: No suspect asbestos-containing materials were observed in the following areas: NB-82, storage room next to kitchen hall, oxygen storage room in warehouse, NB-103, NB-109, and NE foyer exit of emergency area.**