TOILET ACCESSORY SCHEDULE

T.A. #	ACCESSORY DESCRIPTION	MANUFACTURER	MODEL	QUANTITY	MOUNTING HEIGHT HEIGHT	REMARKS	RESPONSIBILITY PURCHASED BY	PLACED BY	INSTALLED BY	BLOCKING TYPE	COMMENTS
100											
GUEST / BARIATRIC RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
100A											
GUEST/ BARIATRIC RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-5	Grab Bar 36"	Bobrick	B-6806 x 36	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-7	Grab Bar 48"	Bobrick	B-6806 x 48	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	2	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7D	Folding Shower Seat with Slat - Bariatric - Rectangular Shape	Bradley Corporation	958	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
TA-40	Underlavatory Insulated Pipe Cover	Plumberex		1		Below Sink	Contractor	Contractor	Contractor		
101											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
101A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
102											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
102A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
103											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
103A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
104											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
104A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30" - Tub Lower Grab Bar	Bobrick	B-6806 x 30	1	2' - 2"	To Top of Tubing. Bottom of Tubing to be 9" above Bathtub Rim	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
105											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
105A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	2	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
106											
RESIDENT RM											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
106A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	2	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
107											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
107A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
108											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
108A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
109											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	

LOCKER SCHEDULE

NUMBER	STYLE	QUANT.	WIDTH	DEPTH	MATL.	HEIGHT	CONST.	PURCHASED BY	PLACED BY	INSTALLED BY	COMMENTS
134											
STAFF LOUNGE											
B1	B	8	1' - 0"	1' - 0"	M	5' - 6"	AW	OWNER	CONTRACTOR	CONTRACTOR	5% MIN TO BE ADA ACCESSIBLE LOCKERS

TOILET ACCESSORY SCHEDULE

T.A. #	ACCESSORY DESCRIPTION	MANUFACTURER	MODEL	QUANTITY	MOUNTING HEIGHT HEIGHT	REMARKS	RESPONSIBILITY PURCHASED BY	PLACED BY	INSTALLED BY	BLOCKING TYPE	COMMENTS
109A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
110											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
110A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
111											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
111A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
112											
RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
112A											
RESIDENT TLT											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-7	Grab Bar 48"	Bobrick	B-6806 x 48	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
TA-28	Underlavatory Insulated Pipe Cover	Plumberex	Refer to Plumbing Schedule	1		Below Sink	Contractor	Contractor	Contractor	-	
113											
BARIATRIC RESIDENT RM											
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
113A											
BARIATRIC RESIDENT TLT RM											
TA-1B	Framed Rectangular Mirror	Gatco	4059MXFS; Elevate	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 18	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-5	Grab Bar 36"	Bobrick	B-6806 x 36	2	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	2	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	3	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7D	Folding Shower Seat with Slat - Bariatric - Rectangular Shape	Bradley Corporation	958	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
122A											
MEDS											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
123											
SPA											
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	2	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-13A-2	Towel Bar - 24"	Bobrick	B-7673 x 24	2	4' - 0"	To CL of Tubing	Contractor	Contractor	Contractor	A	
123A											
SPA TLT											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-3	Grab Bar 24"	Bobrick	B-6806 x 24	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-4	Grab Bar 30"	Bobrick	B-6806 x 30	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
TA-6D	Grab Bar Wall Mounted Swing Up	Bobrick	B-4998	2	2' - 9"	To CL of Upper Tubing	Contractor	Contractor	Contractor	C	
TA-7A-2	Folding Shower Seat with Pad	Bobrick	B-517 / B-518	1	1' - 6"	To Top of Seat	Contractor	Contractor	Contractor	C	
TA-28	Underlavatory Insulated Pipe Cover	Plumberex	Refer to Plumbing Schedule	1		Below Sink	Contractor	Contractor	Contractor	-	
127											
TOILET											
TA-1A-4	Glass Mirror with Stainless Steel Frame	Bobrick	B-165 2430	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-5	Grab Bar 36"	Bobrick	B-6806 x 36	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
132A											
TOILET											
TA-1A-4	Glass Mirror with Stainless Steel Frame	Bobrick	B-165 2430	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-5	Grab Bar 36"	Bobrick	B-6806 x 36	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
133											
STAFF TLT											
TA-1A-4	Glass Mirror with Stainless Steel Frame	Bobrick	B-165 2430	1	3' - 4"	To Bottom of Reflective Surface	Contractor	Contractor	Contractor	B	
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
TA-5A-2	Toilet Tissue Dispenser - Single Roll	Bobrick	B-273	1	1' - 4"	To Top of Unit	Owner	Contractor	Contractor	B	
TA-6A-5	Grab Bar 36"	Bobrick	B-6806 x 36	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6A-6	Grab Bar 42"	Bobrick	B-6806 x 42	1	2' - 10"	To Top of Tubing	Contractor	Contractor	Contractor	C	
TA-6B-2	Grab Bar 24" - Vertical	Bobrick	B-6806 x 24	1	3' - 3"	To Bottom of Tubing	Contractor	Contractor	Contractor	C	
134											
STAFF LOUNGE											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
135											
RESIDENT CORRIDOR											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	2	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	2	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
136											
RESIDENT LAUNDRY											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
138											
PANTRY											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	1	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	1	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	
139											
TOUCHDOWN											
TA-9B-2	Robe Hook Double	Bobrick	B-7672	1	6' - 0"	To Top of Unit (Typical Height)	Contractor	Contractor	Contractor	A	
168											
RESIDENT CORRIDOR											
TA-2C	Surface Mounted Soap Dispenser	Bobrick	B-2111	2	4' - 2 7/8"	To Top of Unit	Owner	Contractor	Contractor	A	
TA-3A	Paper Towel Dispenser	Bobrick	B-262	2	3' - 8"	To Dispensing Slot	Owner	Contractor	Contractor	A	

PRINTS OF THIS DRAWING SHALL NOT BE USED FOR ANY PURPOSE WHATSOEVER WITHOUT THE SEAL AND SIGNATURE OF THE PROFESSIONAL ENGINEEER

Revision 1 | Date 1
Revisions: | Date:

8/1/2024 10:44:49 AM

CONSULTAN