

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

BPA NO.

1. CONTRACT ID CODE

PAGE OF PAGES

2. AMENDMENT/MODIFICATION NUMBER
0002

3. EFFECTIVE DATE

4. REQUISITION/PURCHASE REQ. NUMBER

5. PROJECT NUMBER (if applicable)
503-24-105

6. ISSUED BY CODE

36C244

7. ADMINISTERED BY (If other than Item 6)

CODE 36C244

Department of Veterans Affairs
Network Contracting Office 4Department of Veterans Affairs
Network Contracting Office 4

8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)

To all Offerors/Bidders

(X)

9A. AMENDMENT OF SOLICITATION NUMBER

36C24425R0003

9B. DATED (SEE ITEM 11)

10A. MODIFICATION OF CONTRACT/ORDER NUMBER

10B. DATED (SEE ITEM 13)

CODE

FACILITY CODE

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified. 11/15/2024 16:30 EST

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE

 A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A. B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b). C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: D. OTHER (Specify type of modification and authority)**E. IMPORTANT:** Contractor is not, is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

The purpose of this amendment is to change the due date of this solicitation and provide answers to submitted questions.

1. The proposal due date is changed to November 15h 2024 16:30 EST.

2. Please see the attached document for RFI answers.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)

16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)

Elijah Mcintosh

15B. CONTRACTOR/OFFEROR

15C. DATE SIGNED

16B. UNITED STATES OF AMERICA

16C. DATE SIGNED

(Signature of person authorized to sign)

(Signature of Contracting Officer)

RFI QUESTIONS AND ANSWERS

Questions	Answers
Is it possible to get a core test? It's not indicated what the thickness of the existing roofs are? Some areas may have 2 layers of roof according to my observation on the drain sumps depth	The VA will not be performing a core test.
The drawing calls out for mechanically fastened ISO to concrete deck, is it acceptable to use adhesive instead?	Revised drawings do not call out mechanically fastened. Refer to specifications.
On the roof area over the canopy there was a lot of trim and fascia, are we to replace everything or only the drip edge?	Replace any trim and/or fascia that will need removed with existing roof and reinstalled with new roof to provide a roofing system that meets VA specifications.
On the roof in the back of the building they're building new trays, what is going on those? The reason I'm asking is that if it's ductwork, it may restrict access to that area and it's already very difficult to work around all those curbs and units there.	The steel supports are being installed for new steam lines. Drawings from project 503-19-108 that relate to that roof are attached.
Is it known if the existing deck is sloped or do we need tapered ISO?	In other areas of the building, the deck is sloped on the edges. Tapered ISO will be needed as well to provide proper drainage.
Is TPO a suitable replacement for EPDM?	No

End of Document